

State of New Mexico
Energy, Minerals and Natural Resources Department

Susana Martinez
Governor

Tony Delfin
Acting Cabinet Secretary

David R. Catanach, Division Director
Oil Conservation Division



New Mexico Oil Conservation Division approval and conditions listed below are made in accordance with OCD Rule 19.15.7.11 and are in addition to the actions approved by BLM on the following 3160-3 APD form.

Operator Signature Date: 11-3-16

Well information:

Operator WXP, Well Name and Number W Lybrook Unit #713H

API# 30-045-35808, Section 8, Township 23 N/S, Range 8 E/W

Conditions of Approval: (See the below checked and handwritten conditions)

- ☒ Notify Aztec OCD 24hrs prior to casing & cement.
- ☒ Hold C-104 for directional survey & "As Drilled" Plat
- ☒ Hold C-104 for NSI, NSP, DHC
- ☐ Spacing rule violation. Operator must follow up with change of status notification on other well to be shut in or abandoned
- ☐ Regarding the use of a pit, closed loop system or below grade tank, the operator must comply with the following as applicable:
 - A pit requires a complete C-144 be submitted and approved prior to the construction or use of the pit, pursuant to 19.15.17.8.A
 - A closed loop system requires notification prior to use, pursuant to 19.15.17.9.A
 - A below grade tank requires a registration be filed prior to the construction or use of the below grade tank, pursuant to 19.15.17.8.C
- ☐ Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string
- ☐ Submit Gas Capture Plan form prior to spudding or initiating recompletion operations
- ☒ Regarding Hydraulic Fracturing, review EPA Underground Injection Control Guidance 84
- ☒ Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.
- ☒ Well-bore communication is regulated under 19.15.29 NMAC. This requires well-bore Communication to be reported in accordance with 19.15.29.8.

Charles Stern
NMOCD Approved by Signature

12-9-2016
Date

DEC 08 2016

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NOG14031908
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name EASTERN NAVAJO
2. Name of Operator WPX ENERGY LLC		7. If Unit or CA Agreement, Name and No. INITAL MANCOS PA / NMNM135216A
3a. Address 720 S Main Aztec NM 87410		8. Lease Name and Well No. W LYBROOK UT 713H
3b. Phone No. (include area code) (505)333-1822		9. API Well No. 30-045-35808
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface N SESW / 1215 FSL / 1386 FWL / LAT 36.237674 / LONG -107.708855 At proposed prod. zone SWSE / 1062 FSL / 2331 FEL / LAT 36.251696 / LONG -107.721591		10. Field and Pool, or Exploratory LYBROOK MANCOS W / LYBROOK MA
14. Distance in miles and direction from nearest town or post office* 37.8 miles		11. Sec., T. R. M. or Blk. and Survey or Area SEC 8 / T23N / R8W / NMP
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 20 feet	16. No. of acres in lease 160	12. County or Parish SAN JUAN
17. Spacing Unit dedicated to this well 280	18. Distance from proposed location* to nearest well, drilling, completed, 1215 feet applied for, on this lease, ft.	13. State NM
19. Proposed Depth 5133 feet / 11988 feet	20. BLM/BIA Bond No. on file IND: B001576	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 6823 feet	22. Approximate date work will start* 12/01/2016	23. Estimated duration 30 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Lacey Granillo / Ph: (505)333-1816	Date 11/03/2016
Title Permitting Tech III		
Approved by (Signature) <i>[Signature]</i>	Name (Printed/Typed)	Date 12/8/16
Title AFEN	Office FARMINGTON	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

DRILLING OPERATIONS
AUTHORIZED ARE SUBJECT TO
COMPLIANCE WITH ATTACHED
"GENERAL REQUIREMENTS"

BLM'S APPROVAL OR ACCEPTANCE OF THIS
ACTION DOES NOT RELIEVE THE LESSEE AND
OPERATOR FROM OBTAINING ANY OTHER
AUTHORIZATION REQUIRED FOR OPERATIONS
ON FEDERAL AND INDIAN LANDS

This action is subject to technical
and procedural review pursuant to
43 CFR 3165.3 and appeal
pursuant to 43 CFR 3165.4

NMOCDA

District I
1625 N. French Drive, Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II
811 S. First Street, Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV
1220 S. St. Francis Drive, Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department

Form C-102
Revised August 1, 2011

Submit one copy to
Appropriate District Office

OIL CONSERVATION DIVISION
1220 South St. Francis Drive
Santa Fe, NM 87505

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

*API Number 30-045-35808		*Pool Code 98157	*Pool Name LYBROOK MANCOS W
*Property Code 315250	*Property Name W LYBROOK UNIT		*Well Number 713H
*GRID No. 120782	*Operator Name WPX ENERGY PRODUCTION, LLC		*Elevation 6823'

¹⁰ Surface Location


U. or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	8	23N	8W		1215	SOUTH	1386	WEST	SAN JUAN

¹¹ Bottom Hole Location If Different From Surface

U. or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	6	23N	8W		1062	SOUTH	2331	EAST	SAN JUAN

¹² Dedicated Acres 280.00 SW/4 SE/4 - Section 6 N/2 NE/4, SE/4 NE/4 - Section 7 N/2 SW/4, SW/4 NW/4 - Section 8		¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No. R-14051 - 12,807.24 Acres
---	--	-------------------------------	----------------------------------	--

NO ALLOWABLE WILL BE ASSIGNED
TO THIS COMPLETION UNTIL ALL
INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS
BEEN APPROVED BY THE DIVISION



¹⁷ OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom-hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: *[Signature]* Date: 11-3-16
Printed Name: *[Name]*
E-mail Address: *[Email]*

¹⁸ SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision and that the same is true and correct to the best of my belief.

Date Revised: NOVEMBER 2, 2016
Survey Date: OCTOBER 24, 2016

Signature and Seal of Professional Surveyor



JASON C. EDWARDS
Certificate Number 15269



WPX Energy

Operations Plan

(Note: This procedure will be adjusted onsite based upon actual conditions)

Date: November 3, 2016
Well Name: W Lybrook #713H
SH Location: SESW Sec 8 23N-08W
BH Location: SWSE Sec 6 23N-08W

Field: Lybrook Mancos W
Surface:
Elevation: 6823' GR
Minerals:

Measured Depth: 11,988.26'

I. GEOLOGY

Surface formation - NACIMIENTO

A. FORMATION TOPS: (GR)

NAME	MD	TVD	NAME	MD	TVD
OJO ALAMO	858.00	858.00	POINT LOOKOUT	3,993.00	3,845.00
KIRTLAND	1,066.00	1,066.00	MANCOS	4,196.00	4,032.00
PICTURED CLIFFS	1,442.00	1,442.00	GALLUP	4,575.00	4,381.00
LEWIS	1,553.00	1,553.00	KICKOFF POINT	4,518.55	4,328.02
CHACRA	1,814.00	1,812.00	TOP TARGET	5,541.00	5,108.00
CLIFF HOUSE	2,950.00	2,887.00	LANDING POINT	5,757.98	5,149.00
MENEFEE	3,003.00	2,936.00	BASE TARGET	5,757.98	5,149.00
			TD	11,988.26	5,133.00

B. MUD LOGGING PROGRAM:

Mudlogger on location from surface csg to TD.

C. LOGGING PROGRAM:

LWD GR from surface casing to TD.

D. NATURAL GAUGES:

Gauge any noticeable increases in gas flow. Record all gauges in Tour book and on morning reports.

II. DRILLING

A. MUD PROGRAM:

LSND mud (WBM) will be used to drill the 12-1/4" Surface hole, the 8 3/4" Directional Vertical hole, and the curve portion of the wellbore. A LSND (WBM) or (OBM) will be used to drill the lateral portion of well. Treat for lost circulation as necessary. Obtain 100% returns prior to cementing. Notify Engineering of any mud losses.

B. BOP TESTING:

While drill pipe is in use, the pipe rams and the blind rams will be function tested once each trip. The BOPE will be tested to 2,000 psi (High) for 10 minutes and the annular tested to 1,500 psi for 10 minutes. Pressure test surface casing to 1,500 psi for 30 minutes and intermediate casing to 1,500 psi for 30 minutes. Utilize a BOPE Testing Unit with a recording chart and appropriate test plug for testing. All tests and inspections will be recorded in the tour book as to time and results.

III. MATERIALS

A. CASING PROGRAM:

CASING TYPE	OH SIZE (IN)	DEPTH (MD)	CSG SIZE	WEIGHT	GRADE	CONN
SURFACE	12.25"	320.00'	9.625"	36 LBS	J-55 or equiv	STC
INTERMEDIATE	8.75"	5,757.98'	7"	23 LBS	J-55 or equiv	LTC
PRODUCTION	6.125"	5607.98' - 11,988.26'	4.5"	11.6 LBS	P-110 or equiv	LTC
TIE BACK	6.125"	Surf. - 5607.98'	4.5"	11.6 LBS	P-110 or equiv	LTC

B. FLOAT EQUIPMENT:

1. SURFACE CASING:

9-5/8" notched regular pattern guide shoe. Run (1) standard centralizer on each of the bottom (4) joints of Surface Casing.

2. INTERMEDIATE CASING:

7" cement nose guide shoe with a self-fill insert float. Place float collar one joint above the shoe. Install (1) centralizer on each of the bottom (3) joints and one standard centralizer every (3) joints to 2,500 ft. Run (1) centralizer at 2,500 ft., 2,300ft., 2,000ft., 1,500 ft., and 1,000 ft. If losses are encountered during the drilling of the intermediate section a DV tool will be utilized and a 2 stage cement job may be planned to ensure cement circ back to surface. The DV tool will be placed 100' above the top of the Chacra formation. If cement is circulated back to surface on the first stage, a cancellation device will be dropped to shift the dv tool closed and the 2nd stage cement job will be aborted at that time, if no cement is seen at surface on the 1st stage the stage tool will be opened and a 2nd stage cement job will be pumped.

3. PRODUCTION LINER:

Run 4-1/2" Liner with cement nose guide Float Shoe + 2jts. of 4-1/2" casing + Landing Collar + 4-1/2" pup joint + 1 RSI (Sliding Sleeve) positioned inside the 330ft Hard line. Centralizer program will be determined by Wellbore condition and when Lateral is evaluated by Geoscientists and Reservoir Engineers. Set seals on Liner Hanger. Test TOL to 1500 psi for 15 minutes.

C. CEMENT:

(Note: Volumes may be adjusted onsite due to actual conditions)

1. Surface:

5 bbl Fresh Water Spacer, 100 sx (160 cu.ft.) of 14.5 ppg Type I-II (Neat G) + 20% Fly Ash cement w/ 7.41 gal/sack mix water ratio @ 1.61 cu ft/sx yield. Calculated @ volume + 50% excess. WOC 12 hours. Test csg to 600psi. Total Volume: (160 cu-ft/100 sx/ Bbls).TOC at Surface.

2. Intermediate:

Spacer #1: 20 bbl (112 cuft) Chemwash. Lead Cement: 111 bbls, 315 sks, (621 cuft), 12.3 ppg @ 1.97 cuft/sk yield. Tail Cement: 59 bbls, 254 sks, (331 cuft), 13.5 ppg @ 1.3 cuft/sk yield. Displacement: Displace w/ +/- 227 bbl Drilling mud or water. Total Cement: 170 bbls, 570 sks, (952 cuft)

3. Prod Liner:

Spacer #1: 10 bbl (56 cu-ft) Water Spacer. Spacer #2: 40 bbl 9.5 ppg (224.6 cu-ft) Tuned Spacer III. Spacer #3: 10 bbl Water Spacer. Lead Cement: Extencem™ System. Yield 1.36 cuft/sk 13.3 ppg (625 sx /850 cuft /151 bbls). Tail Spacer: 20 BBL of MMCR. Displacement: Displace w/ +/-157bbl Fr Water. Total Cement (625 sx /850bbls).

D. COMPLETION:

Run CCL for perforating

A. PRESSURE TEST:

1. Pressure test 4-1/2" casing to 4500 psi max, hold at 1500 psi for 30 minutes. Increase pressure to Open RSI sleeves.

B. STIMULATION:

1. Stimulate with approximately 2,805,000# 20/40 mesh sand and 340,000# 16/30 mesh sand in 619,113 gallons water with 42,696 mscf N2 for 17 stages.
2. Isolate stages with flow through frac plug.
3. Drill out frac plugs and flowback lateral.

C. RUNNING TUBING:

1. Production Tubing: Run 2-7/8", 6.5#, J-55, EUE tubing with a SN on top of bottom joint. Land tubing near Top of Liner.

If this horizontal well is drilled past the applicable setbacks, an unorthodox location application is not required because the completed interval in this well, as defined by 19.15.16.7 B(1) NMAC, will be entirely within the applicable setbacks. This approach complies with all applicable rules, including 19.15.16.14 A(3) NMAC, 19.15.16.14 B(2) NMAC, 19.15.16.15 B(2) NMAC, and 19.15.16.15. B(4) NMAC.

NOTES:

A 4-1/2" 11.6# P-110 Liner will be run to TD and landed +/- 150 ft. into the 7" 23# J-55 Intermediate casing with a Liner Hanger and pack-off assembly then cemented to top of liner hanger.

After cementing and TOL clean up operations are complete, the TOL will be tested to 1500 psi (per BLM).

Well Name: W Lybrook UT #713H
 Surface Location: 2308-08N WLU
 NAD 1927 (NADCON CONUS), US State Plane 1927 (Exact solution) New Mexico West 3003
 Ground Elevation: 6823.00
 +N/-S +E/-W Northing Easting Latitude Longitude Slot
 0.00 0.00 1905774.15 536889.70 36.237661 -107.708243 713H
 GL @ 6823.00usft (Original Well Elev)


Project: T23N R8W
 Site: 2308-08N WLU
 Well: W Lybrook UT #713H
 Plan: Plan #2 26Oct16 kjs

ANNOTATIONS

TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation
1400.00	1400.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 2.00
2530.99	2562.65	23.25	84.76	21.27	231.73	-120.18	232.70	Hold 23.25° Inc, 84.76° Az
4328.02	4518.55	23.25	84.76	91.84	1000.67	-518.96	1004.88	KOP 9°/100
5033.71	5363.01	60.00	315.25	415.71	892.97	-194.25	1423.35	Hold 60° Tangent @ 60° Inc
5063.71	5423.01	60.00	315.25	452.62	856.39	-142.85	1475.31	Begin 9°/100 Build
5149.00	5757.98	90.15	315.25	679.84	631.15	173.65	1795.26	POE 90.15° Inc, 315.25° Az
5133.00	11988.26	90.15	315.25	5104.61	-3754.92	6336.92	8025.52	TD at 11988.26



Azimuths to True North
 Magnetic North: 9.29°
 Magnetic Field
 Strength: 50029.3snT
 Dip Angle: 62.94°
 Date: 9/23/2015
 Model: IGRF2010



DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
Start 60 tan 713H	5033.71	415.71	892.97	1906191.02	537782.13	36.238803	-107.705215	Point
BHL 713H	5133.00	5104.61	-3754.92	1910873.91	533128.19	36.251683	-107.720976	Point
POE 713H	5149.00	679.85	631.15	1906454.81	537519.97	36.239529	-107.706103	Point



WPX Energy

T23N R8W

2308-08N WLU

W Lybrook UT #713H - Slot 713H

Wellbore #1

Plan: Plan #2 26Oct16 kjs

Standard Planning Report - Geographic

28 October, 2016

Database:	COMPASS	Local Co-ordinate Reference:	Well W Lybrook UT #713H - Slot 713H
Company:	WPX Energy	TVD Reference:	GL @ 6823.00usft (Original Well Elev)
Project:	T23N R8W	MD Reference:	GL @ 6823.00usft (Original Well Elev)
Site:	2308-08N WLU	North Reference:	True
Well:	W Lybrook UT #713H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #2 26Oct16 kjs		

Project		T23N R8W	
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico West 3003		

Site		2308-08N WLU				
Site Position:		Northing:	1,906,343.71 usft	Latitude:	36.239225	
From:	Map	Easting:	537,196.07 usft	Longitude:	-107.707202	
Position Uncertainty:		0.00 usft	Slot Radius:	13.200 in	Grid Convergence:	0.07 °

Well	W Lybrook UT #713H - Slot 713H					
Well Position	+N/-S	0.00 usft	Northing:	1,905,774.15 usft	Latitude:	36.237661
	+E/-W	0.00 usft	Easting:	536,889.70 usft	Longitude:	-107.708243
Position Uncertainty		0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level:	6,823.00 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	9/23/2015	9.29	62.94	50,029

Design	Plan #2 26Oct16 kjs			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (bearing)
	0.00	0.00	0.00	323.66

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,562.65	23.25	84.76	2,530.99	21.27	231.73	2.00	2.00	0.00	84.76	
4,518.55	23.25	84.76	4,328.02	91.84	1,000.67	0.00	0.00	0.00	0.00	
5,363.01	60.00	315.25	5,033.71	415.71	892.97	9.00	4.35	-15.34	-136.48	Start 60 tan 713H
5,423.01	60.00	315.25	5,063.71	452.62	856.39	0.00	0.00	0.00	0.00	
5,757.98	90.15	315.25	5,149.00	679.84	631.15	9.00	9.00	0.00	0.00	
11,988.26	90.15	315.25	5,133.00	5,104.61	-3,754.92	0.00	0.00	0.00	0.00	BHL 713H

Database:	COMPASS	Local Co-ordinate Reference:	Well W Lybrook UT #713H - Slot 713H
Company:	WPX Energy	TVD Reference:	GL @ 6823.00usft (Original Well Elev)
Project:	T23N R8W	MD Reference:	GL @ 6823.00usft (Original Well Elev)
Site:	2308-08N WLU	North Reference:	True
Well:	W Lybrook UT #713H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #2 26Oct16 kjs		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
200.00	0.00	0.00	200.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
351.00	0.00	0.00	351.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
9 5/8"									
400.00	0.00	0.00	400.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
600.00	0.00	0.00	600.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
800.00	0.00	0.00	800.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
1,000.00	0.00	0.00	1,000.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
1,200.00	0.00	0.00	1,200.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
1,400.00	0.00	0.00	1,400.00	0.00	0.00	1,905,774.15	536,889.70	36.237661	-107.708243
Start Build 2.00									
1,600.00	4.00	84.76	1,599.84	0.64	6.95	1,905,774.80	536,896.65	36.237663	-107.708220
1,800.00	8.00	84.76	1,798.70	2.55	27.76	1,905,776.74	536,917.46	36.237668	-107.708149
2,000.00	12.00	84.76	1,995.62	5.72	62.34	1,905,779.95	536,952.04	36.237677	-107.708032
2,200.00	16.00	84.76	2,189.64	10.14	110.51	1,905,784.44	537,000.20	36.237689	-107.707869
2,400.00	20.00	84.76	2,379.82	15.79	172.05	1,905,790.16	537,061.73	36.237704	-107.707660
2,562.65	23.25	84.76	2,530.99	21.27	231.73	1,905,795.72	537,121.40	36.237720	-107.707457
Hold 23.25° Inc, 84.76° Az									
2,600.00	23.25	84.76	2,565.31	22.62	246.42	1,905,797.09	537,136.09	36.237723	-107.707408
2,800.00	23.25	84.76	2,749.07	29.83	325.04	1,905,804.40	537,214.71	36.237743	-107.707141
3,000.00	23.25	84.76	2,932.82	37.05	403.67	1,905,811.72	537,293.33	36.237763	-107.706874
3,200.00	23.25	84.76	3,116.57	44.26	482.30	1,905,819.04	537,371.94	36.237783	-107.706608
3,400.00	23.25	84.76	3,300.33	51.48	560.93	1,905,826.36	537,450.56	36.237803	-107.706341
3,600.00	23.25	84.76	3,484.08	58.70	639.55	1,905,833.68	537,529.18	36.237822	-107.706075
3,800.00	23.25	84.76	3,667.84	65.91	718.18	1,905,840.99	537,607.80	36.237842	-107.705808
4,000.00	23.25	84.76	3,851.59	73.13	796.81	1,905,848.31	537,686.42	36.237862	-107.705541
4,200.00	23.25	84.76	4,035.34	80.35	875.44	1,905,855.63	537,765.04	36.237882	-107.705275
4,400.00	23.25	84.76	4,219.10	87.58	954.07	1,905,862.95	537,843.65	36.237902	-107.705008
4,518.55	23.25	84.76	4,328.02	91.84	1,000.67	1,905,867.28	537,890.25	36.237913	-107.704850
KOP 9°/100									
4,600.00	18.60	68.76	4,404.14	98.02	1,028.83	1,905,873.50	537,918.40	36.237930	-107.704755
4,800.00	17.65	8.45	4,595.79	139.92	1,063.29	1,905,915.44	537,952.81	36.238045	-107.704638
5,000.00	30.15	334.97	4,779.06	216.05	1,046.37	1,905,991.55	537,935.79	36.238255	-107.704695
5,200.00	46.22	321.57	4,936.03	318.96	979.70	1,906,094.37	537,868.99	36.238537	-107.704921
5,363.01	60.00	315.25	5,033.71	415.71	892.97	1,906,191.02	537,782.13	36.238803	-107.705215
Hold 60° Tangent @ 60° Inc									
5,400.00	60.00	315.25	5,052.20	438.47	870.41	1,906,213.74	537,759.55	36.238866	-107.705292
5,423.01	60.00	315.25	5,063.71	452.62	856.39	1,906,227.88	537,745.50	36.238904	-107.705339
Begin 9°/100 Build									
5,600.00	75.93	315.25	5,129.90	568.76	741.26	1,906,343.87	537,630.23	36.239224	-107.705730
5,757.98	90.15	315.25	5,149.00	679.84	631.15	1,906,454.81	537,519.97	36.239529	-107.706103
POE 90.15° Inc, 315.25° Az									
5,758.00	90.15	315.25	5,149.00	679.86	631.13	1,906,454.83	537,519.95	36.239529	-107.706103
7"									
5,800.00	90.15	315.25	5,148.89	709.69	601.56	1,906,484.62	537,490.35	36.239611	-107.706203
6,000.00	90.15	315.25	5,148.38	851.73	460.76	1,906,626.48	537,349.37	36.240001	-107.706681
6,200.00	90.15	315.25	5,147.86	993.77	319.97	1,906,768.33	537,208.39	36.240391	-107.707158
6,400.00	90.15	315.25	5,147.35	1,135.81	179.17	1,906,910.19	537,067.40	36.240781	-107.707636
6,600.00	90.15	315.25	5,146.84	1,277.85	38.37	1,907,052.05	536,926.42	36.241172	-107.708113
6,800.00	90.15	315.25	5,146.32	1,419.89	-102.43	1,907,193.91	536,785.44	36.241562	-107.708591
7,000.00	90.15	315.25	5,145.81	1,561.93	-243.23	1,907,335.77	536,644.46	36.241952	-107.709068
7,200.00	90.15	315.25	5,145.30	1,703.97	-384.03	1,907,477.63	536,503.48	36.242342	-107.709546
7,400.00	90.15	315.25	5,144.78	1,846.01	-524.82	1,907,619.49	536,362.50	36.242732	-107.710023

Database:	COMPASS	Local Co-ordinate Reference:	Well W Lybrook UT #713H - Slot 713H
Company:	WPX Energy	TVD Reference:	GL @ 6823.00usft (Original Well Elev)
Project:	T23N R8W	MD Reference:	GL @ 6823.00usft (Original Well Elev)
Site:	2308-08N WLU	North Reference:	True
Well:	W Lybrook UT #713H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #2 26Oct16 kjs		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
7,600.00	90.15	315.25	5,144.27	1,988.05	-665.62	1,907,761.35	536,221.51	36.243123	-107.710500
7,800.00	90.15	315.25	5,143.76	2,130.09	-806.42	1,907,903.20	536,080.53	36.243513	-107.710978
8,000.00	90.15	315.25	5,143.24	2,272.13	-947.22	1,908,045.06	535,939.55	36.243903	-107.711455
8,200.00	90.15	315.25	5,142.73	2,414.18	-1,088.02	1,908,186.92	535,798.57	36.244293	-107.711933
8,400.00	90.15	315.25	5,142.21	2,556.22	-1,228.82	1,908,328.78	535,657.59	36.244683	-107.712410
8,600.00	90.15	315.25	5,141.70	2,698.26	-1,369.61	1,908,470.64	535,516.61	36.245074	-107.712888
8,800.00	90.15	315.25	5,141.19	2,840.30	-1,510.41	1,908,612.50	535,375.62	36.245464	-107.713365
9,000.00	90.15	315.25	5,140.67	2,982.34	-1,651.21	1,908,754.36	535,234.64	36.245854	-107.713843
9,200.00	90.15	315.25	5,140.16	3,124.38	-1,792.01	1,908,896.22	535,093.66	36.246244	-107.714320
9,400.00	90.15	315.25	5,139.65	3,266.42	-1,932.81	1,909,038.07	534,952.68	36.246634	-107.714798
9,600.00	90.15	315.25	5,139.13	3,408.46	-2,073.61	1,909,179.93	534,811.70	36.247024	-107.715276
9,800.00	90.15	315.25	5,138.62	3,550.50	-2,214.41	1,909,321.79	534,670.72	36.247415	-107.715753
10,000.00	90.15	315.25	5,138.11	3,692.54	-2,355.20	1,909,463.65	534,529.73	36.247805	-107.716231
10,200.00	90.15	315.25	5,137.59	3,834.58	-2,496.00	1,909,605.51	534,388.75	36.248195	-107.716708
10,400.00	90.15	315.25	5,137.08	3,976.62	-2,636.80	1,909,747.37	534,247.77	36.248585	-107.717186
10,600.00	90.15	315.25	5,136.57	4,118.66	-2,777.60	1,909,889.23	534,106.79	36.248975	-107.717663
10,800.00	90.15	315.25	5,136.05	4,260.70	-2,918.40	1,910,031.09	533,965.81	36.249365	-107.718141
11,000.00	90.15	315.25	5,135.54	4,402.74	-3,059.20	1,910,172.94	533,824.83	36.249756	-107.718618
11,200.00	90.15	315.25	5,135.02	4,544.78	-3,199.99	1,910,314.80	533,683.84	36.250146	-107.719096
11,400.00	90.15	315.25	5,134.51	4,686.83	-3,340.79	1,910,456.66	533,542.86	36.250536	-107.719573
11,600.00	90.15	315.25	5,134.00	4,828.87	-3,481.59	1,910,598.52	533,401.88	36.250926	-107.720051
11,800.00	90.15	315.25	5,133.48	4,970.91	-3,622.39	1,910,740.38	533,260.90	36.251316	-107.720529
11,988.26	90.15	315.25	5,133.00	5,104.61	-3,754.92	1,910,873.91	533,128.19	36.251684	-107.720978
TD at 11988.26									

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (bearing)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Start 60 tan 713H - plan hits target center - Point	0.00	0.00	5,033.71	415.71	892.97	1,906,191.02	537,782.13	36.238803	-107.705215
BHL 713H - plan hits target center - Point	0.00	0.00	5,133.00	5,104.61	-3,754.92	1,910,873.91	533,128.19	36.251684	-107.720978
POE 713H - plan hits target center - Point	0.00	0.00	5,149.00	679.85	631.15	1,906,454.81	537,519.97	36.239529	-107.706103

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (in)	Hole Diameter (in)	
351.00	351.00	9 5/8"	9.625	12.250	
5,758.00	5,149.00	7"	7.000	8.750	

Database:	COMPASS	Local Co-ordinate Reference:	Well W Lybrook UT #713H - Slot 713H
Company:	WPX Energy	TVD Reference:	GL @ 6823.00usft (Original Well Elev)
Project:	T23N R8W	MD Reference:	GL @ 6823.00usft (Original Well Elev)
Site:	2308-08N WLU	North Reference:	True
Well:	W Lybrook UT #713H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #2 26Oct16 kjs		

Plan Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
1,400.00	1,400.00	0.00	0.00	Start Build 2.00
2,562.65	2,530.99	21.27	231.73	Hold 23.25° Inc, 84.76° Az
4,518.55	4,328.02	91.84	1,000.67	KOP 9°/100
5,363.01	5,033.71	415.71	892.97	Hold 60° Tangent @ 60° Inc
5,423.01	5,063.71	452.62	856.39	Begin 9°/100 Build
5,757.98	5,149.00	679.84	631.15	POE 90.15° Inc, 315.25° Az
11,988.26	5,133.00	5,104.61	-3,754.92	TD at 11988.26

Once the bore is completed and cased, the anode is installed in accordance with the manufacturer's specifications. The bore is then backfilled with Conducrete using a tremie tube technique starting from TD of the bore. The casing will be cut and capped 12 inches below the surface. The specified flush grade valve box is then installed directly over the bed. The bed location (Lat/Long) is recorded and full drill log report is completed and filed with WPX. The bed will not be energized for a minimum of 45 days.

After the completion phases and pipeline installation, portions of the project areas not needed for operation will be reclaimed. When the well is plugged, final reclamation will occur within the remainder of the project areas. Reclamation is described in detail in the Surface Use Reclamation Plan (Appendix A).

7.0 Methods for Handling Waste

A. Cuttings

1. Drilling operations will utilize a closed-loop system. Drilling of the horizontal laterals will be accomplished with water-based mud. All cuttings will be placed in roll-off bins and hauled to a commercial disposal facility or a land farm. WPX will follow Onshore Oil and Gas Order No. 1 regarding the placement, operation, and removal of closed-loop systems. No blow pit will be used.
2. Closed-loop tanks will be adequately sized for containment of all fluids.

B. Drilling Fluids

1. Drilling fluids will be stored onsite in above-ground storage tanks. Upon termination of drilling operations, the drilling fluids will be recycled and transferred to other permitted closed-loop systems or returned to the vendor for reuse, as practical. All residual fluids will be hauled to a commercial disposal facility.

C. Spills

1. Any spills of non-freshwater fluids will be immediately cleaned up and removed to an approved disposal site.

D. Sewage

1. Portable toilets will be provided and maintained during construction, as needed (see Figure 3 in Appendix B for the location of toilets).

E. Garbage and other water material


1. All garbage and trash will be placed in a metal trash basket. The trash and garbage will be hauled off site and dumped in an approved landfill, as needed.


F. Hazardous Waste

1. No chemicals subject to reporting under Superfund Amendments and Reauthorization Act Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of these wells.
2. No extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of these wells.
3. All fluids (i.e., scrubber cleaners) used during washing of production equipment will be properly disposed of to avoid ground contamination or hazard to livestock or wildlife.

G. Produced Water:

1. WPX Energy will dispose of produced water from this well at one of the following facilities:
 - a. Lybrook Yard WDW #1, API #30-039-27533, NMOCD permit #SWD-907, operated by Elm Ridge Resources, located in NE ¼, Section 14, Township 23 North, Range 7 West
 - b. Jillson Federal #1, NMOCD order #R-10168, operated by ConocoPhillips, located in NW ¼, Section 8, Township 24 North, Range 3 West
 - c. Basin Disposal, permit #NM-01-005, located in the NW ¼, Section 3, Township 29 North, Range 11 West
 - d. Sunco SWD #001, API #30-045-28653, NMOCD permit SWD-457, operated by Key Energy, located in NW ¼, Section 2, Township 29 North, Range 12 West
2. Water will be hauled by truck. Some produced water may also be used in drilling and completion operations as an alternative disposal method.





Directions from the Intersection of US Hwy 550 & US Hwy 64
in Bloomfield, NM to WPX Energy Production, LLC W Lybrook Unit #713H
1215' FSL & 1386' FWL, Section 8, T23N, R8W, N.M.P.M., San Juan County, NM

Latitude: 36.237674°N Longitude: 107.708855°W Datum: NAD1983

From the intersection of US Hwy 550 & US Hwy 64 in Bloomfield, NM. travel Southerly on US Hwy 550 for 38.7 miles to Mile Marker 112.7;

Go Right (Southerly) on County Road #7900 for 0.2 miles to begin proposed access on right-hand side of County Road #7900 which continues for 764.1' to staked WPX W Lybrook Unit #713H location.