

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill, or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE

1. TYPE OF WELL Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other: _____		5. LEASE SERIAL NO. NM18317
2. NAME OF OPERATOR Black Hills Gas Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME ---
3. ADDRESS AND TELEPHONE NO. 350 Indiana Street, Suite 400 Golden CO 80401 CONTACT: Lynn Benally PHONE: 505.634.1111 Fax: 505.634.1116		7. IF UNIT OR CA, AGREEMENT DESIGNATION -
4. LOCATION OF WELL (Footage, T, R, M, or Survey Description) 980' FNL 790' FEL Sec. 14 T 29N R 4W		8. WELL NAME AND NO. 29-4 Conoco 14 10 aka(Carson 29-04-14 10H)
11. COUNTY OR PARISH, STATE Rio Arriba, New Mexico		9. API WELL NO. 30-039-21586
10. FIELD AND POOL, OR EXPLORATORY AREA <i>El Estano PC</i>		

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (start/resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with the BLM/BIA.

Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The location was permitted for Continental Oil Company with an Application for Permit to Drill (APD) submitted to the Bureau of Land Management (BLM) in Farmington, New Mexico, and the New Mexico Oil Conservation Division (NMOCD) on December 13, 1977. The APD was given API#30-039-21586. Black Hills Gas Resources, Inc. (BHGR) proposes to re-enter and horizontally drill this location with a northwesterly lateral bore. End of lateral bore is anticipated to be 660' FNL 528' FWL of Sec. 14 T29N R4W. Please find attached: Revised Drilling Program; BOP Diagram, Hydrogen Sulfide Drilling Operations Plan and Horizontal Drilling plan.

Please send a copy of all correspondence to Banko Petroleum Management Inc. at 385 Inverness Parkway, Suite 420, Englewood, CO 80112-5849. Please contact Dave Banko or Kathy Schneebeck at 303-820-4480, or at david@banko1.com or kathys@banko1.com, respectively, if you have any questions. Thank you.

CONDITIONS OF APPROVAL

Adhere to previously issued stipulations.

14. I hereby certify that the foregoing is true and correct	
Name (Printed/Typed) Kathy L. Schneebeck, 303.820.4480	Title: Permit Agent for Black Hills Gas Resources, Inc.
Signature <i>Kathy L. Schneebeck</i>	Date: February 27, 2006

THIS SPACE FOR FEDERAL OR STATE OFFICE USE.

Approved by <i>Matt Habbert</i>	Title <i>PETE ENG</i>	Date <i>3/23/06</i>
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office <i>BLM - FFO</i>	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious, or fraudulent statements or representations as to any matter within its jurisdiction.

HOLD C104 FOR *directional survey*
NMOCD

DISTRICT I
1625 N. French Dr., Hobbs, N.M. 88240

DISTRICT II
1301 W. Grand Ave., Artesia, N.M. 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT IV
1220 South St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised October 12, 2005

Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies

☒ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-039-21586		² Pool Code 72400		³ Pool Name East Blanco Pictured Cliffs	
⁴ Property Code 301950		⁵ Property Name 29-4 CONOCO 14 29 4			⁶ Well Number 10
⁷ GRID No. 13925		⁸ Operator Name BLACK HILLS GAS RESOURCES			⁹ Elevation 7435'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	14	29-N	4-W		980	NORTH	790	EAST	RIO ARRIBA

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	14	29-N	4-W		660	NORTH	528	WEST	RIO ARRIBA

¹² Dedicated Acres 320	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
--------------------------------------	-------------------------------	----------------------------------	-------------------------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>16</p> <p>528' B.H.L.</p> <p>790'</p> <p>980'</p> <p>320</p> <p>N 89-33-52 W 5147.9' (C)</p> <p>CALC. CORNER BY DBL. PROP.</p> <p>NOTE: SURFACE FOOTAGES SHOWN ARE OF RECORD PER REQUEST OF B.L.M. AND PRODUCER.</p> <p>LAT. 36°43'46.2" N (NAD 83) LONG. 107°13'01.9" W (NAD 83)</p> <p>14</p> <p>APR 2006 RECEIVED OIL CONS. DIV. DIST. 3</p> <p>CALC. CORNER BY DBL. PROP.</p>		<p>17 OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or released mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or is a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>February 27, 2006 Signature: <i>Kathy L. Schneebeck</i> Date: _____ Printed Name: Kathy L. Schneebeck Permit Agent for Black Hills Gas Resources, Inc. kathys@banko1.com</p>
<p>18 SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>Date: _____ Signature: <i>John A. Vukovich</i> Professional Surveyor: 14821 7-24-2006 Certificate Number</p>		

DISTRICT I
1625 N. French Dr., Hobbs, N.M. 88240

DISTRICT II
1301 W. Grand Ave., Artesia, N.M. 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT IV
1220 South St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-10
Revised October 12, 2005

Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies

RECEIVED

OTC FARMINGTON NM

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-039-21586		² Pool Code		³ Pool Name	
⁴ Property Code		⁵ Property Name 29-4 CONOCO 14		⁶ Well Number 10	
⁷ GRID No.		⁸ Operator Name BLACK HILLS GAS RESOURCES		⁹ Elevation 7435'	

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	14	29-N	4-W		980	NORTH	790	EAST	RIO ARRIBA

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	14	29-N	4-W		660	NORTH	528	WEST	RIO ARRIBA

¹² Dedicated Acres		¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No.	

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

¹⁶ CALC. CORNER BY DBL. PROP. 660' 528' B.H.L.		N 89-33-52 W 5147.9' (C) CALC. CORNER BY DBL. PROP. 980' 790'		¹⁷ OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. Kathy L. Schneebeck February 27, 2006 Signature Date Kathy L. Schneebeck Printed Name Permit Agent for Black Hills Gas Resources, Inc. kathys@banko1.com	
LAT. 36°43'46.2" N (NAD 83) LONG. 107°13'01.9" W (NAD 83)		NOTE: SURFACE FOOTAGES SHOWN ARE OF RECORD PER REQUEST OF B.L.M. AND PRODUCER.		¹⁸ SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. JONNA VURONICH NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR 14824 2-24-2006 Certificate Number	
See amended 14		CALC. CORNER BY DBL. PROP.			

Black Hills Gas Resources, Inc.
29-4 Conoco 14 10 (aka Carson 29-04-14 10H)
API #30-039-21586
Surface: 980' FNL 790' FEL(NE/4 NE/4)
End of Horizontal Hole: 660' FNL 528' FWL (NW/4 NW/4)
T29N R4W Sec. 14
Rio Arriba County, New Mexico
Lease: NM18317

DRILLING PROGRAM

This Sundry Notice is submitted per CFR 3162.3-2. The existing well pad and reserve pit will be utilized "as is."

This is a horizontal entry into the existing well 29-4 Conoco 14 10 (aka Carson 29-04-14 10H) to the Pictured Cliffs Formation. See also the attached Horizontal Re-completion Plan.

SURFACE FORMATION – San Jose. Surface water protection plan: Surface casing will be cemented to surface.

GROUND ELEVATION – 7,435' GL

ESTIMATED FORMATION TOPS (Water, oil, gas and/or other mineral-bearing formations).

All Depths are True Vertical Depth (TVD)

San Jose	Surface	Sandstone, shales and siltstones
Ojo Alamo	3,314'	Sandstone, shales and siltstones
Kirtland	3,770'	Sandstone, shales and siltstones
Fruitland	3,935'	Sandstone, shales and siltstones
Pictured Cliffs	4,075'	Sandstone, shales and siltstones

TOTAL DEPTH 4,127.94' TVD (end of horizontal hole) 3,843.34' TVD (anticipated horizontal section)
7,776.80' MD

Estimated depths of anticipated fresh water, oil, or gas:

Tertiary

San Jose	1,800'	Gas
Ojo Alamo	3,314'	Gas
Fruitland	3,935'	Gas
Pictured Cliffs	4,075'	Gas

RE-ENTRY – HORIZONTAL DRILLING PROGRAM

- A) A 2,000-psi WP double-gated BOP will be installed on the tubing head with blind rams on bottom and pipe rams on top controlled by an accumulator placed within easy access to drill and other crew members.
- B) No annular preventor will be placed above BOP stack.
- C) Retrievable whipstock to be set at $\pm 3,652'$.
- D) Window to be milled out of 4-1/2" csg at $\pm 3,648'$.
- E) Kick-off Point is estimated to be at 3,648' based on collar locations.

CASING PROGRAM

True Vertical Depth	Hole Diameter	Casing Diameter	Casing Weight and Grade	Cement
0' – 501'	12-3/4"	8-5/8"	K-55 24# ST&C	To surface (previously set)
0' – 4,600'	7-7/8"	4-1/2"	J-55 10.5# ST&C	To surface (previously set)
3,648' – 7,776.80' (MD)	4-3/4"	Open hole	None	None

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and protected.

PRESSURE CONTROL

BOPs and choke manifold will be installed and pressure tested before drilling out under surface casing (subsequent pressure test will be performed whenever pressure seals are broken), and then will be checked daily as to mechanical operating condition. BOP's will be pressure tested at least once every 30 days. Ram type preventors and related pressure control equipment will be pressure tested to 1,000 psi. Annular type preventor will be pressure tested to 50% of the rated working pressure, not to exceed 1,000 psi. All casing strings will be pressure tested to 0.22 psi/ft. or 1,000 psi, whichever is greater, not to exceed 70% of internal yield.

BOP to be either double gate rams or an annular preventor as per Onshore Order No. 2.

Statement on Accumulator System and Location of Hydraulic Controls

The drilling rig has not yet been selected for this well. Selection will take place after approval of this application. Manual and/or hydraulic controls will be in compliance with Onshore Order No. 2 for 2M systems.

A remote accumulator will be used. Pressures, capacities, location of remote hydraulic and manual controls will be identified at the time of the BLM supervised BOP test.

MUD PROGRAM

3,648' - 7,776.80' MD Low solids non-dispersed
M.W. 8.5 – 9.2 ppg
Vis – 28 – 50 sec
W.L. 15cc or less

Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kick" will be available at wellsite.

AUXILIARY EQUIPMENT

- A) A Kelly cock will be kept in the drill string at all times
- B) Inside BOP or stab-in valve (available on rig floor)
- C) Mud monitoring will be visually observed
- D) Testing: None anticipated.

LOGGING, CORING, TESTING PROGRAM

- A) Logging: CBL-CCL log will be run prior to beginning squeeze work.
- B) Coring: None
- C) Testing: None

ABNORMAL CONDITIONS

- A) Pressures: No abnormal conditions are anticipated
Bottom hole pressure gradient – 0.31 psi/ft
- B) Temperatures: No abnormal conditions are anticipated
- C) H₂S: See H₂S Plan if H₂S is encountered.
- D) Estimated bottomhole pressure: 1,280 psi


ANTICIPATED START DATE

March 27, 2006

COMPLETION

The location pad is of sufficient size to accommodate all completion activities and equipment. A string of 2-3/8" J-55 4.7#/ft tubing will be run for a flowing string. A Sundry Notice will be submitted with a revised completion program if warranted.

ANNULAR PREVENTOR MAY BE SUBSTITUTED FOR DOUBLE GATE PREVENTORS
 ROTATING HEAD TO BE USED WHEN AIR/AIR MIST DRILLING



2M CHOKES MANIFOLD EQUIPMENT — CONFIGURATION MAY VARY

BLOWOUT PREVENTER

9-10 inch 2000 psi minimum

Hydrogen Sulfide Drilling Operations Plan

I. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H_2S).
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H_2S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H_2S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H_2S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H_2S zone (within 3 days or 500 feet) and weekly H_2S and well control drills for all personnel in each crew. The initial training sessions shall include a review of the site specific H_2S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

II. H_2S safety equipment and Systems

Note: All H_2S safety equipment and systems (if necessary) will be installed, tested, and operational when drilling reaches a depth of 500 feet above the three days prior to penetrating the first zone containing or reasonably expected to contain H_2S .

A. Well control equipment:

1. Choke manifold with a minimum of one remote choke.
2. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.

B. Protective equipment for essential personnel

1. Mark II Surniveair 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

Black Hills Gas Resources

C. H₂S detection and monitoring equipment:

1. Two portable H₂S monitors positioned on location for best coverage and response. These units have warning lights and aquilbesirens when H₂S levels of 10ppm.

D. Visual warning systems:

1. Wind direction indicators as shown on well site diagram.
2. Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used when appropriate. See example attached.

E. Mud program:

1. The mud programs has been designed to minimize the volume of H₂S circulated to the surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

F. Metallurgy:

1. All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
2. All elastomers used for packing and seals shall be H₂S trim.


G. Communication:

1. Cellular telephone communications in company vehicles.

H. Well testing:

1. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity which are necessary to safely and adequately conduct the test. The drill stem lesting will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill stem testing operations conducted in an H₂S environment will use the closed chamber method of testing.

Job Number: 205-xxx
Company: BHGR
Lease/Well: Many Canyons 29-04-14 Carson #10H
Location: Rio Arriba County, NM




WELL PAD DIAGRAM

COMPANY: BLACK HILLS GAS RESOURCES
 LEASE: 29-4 CONOCO 14 NO. 10 (AKA-CARSON 29-04-14 NO. 10H)
 FOOTAGE: 990 FNL, 735 FEL
 SEC.: 14, TWN: 29-N, RNG: 4-W, NMPM
 ELEVATION: 7435'




SCALE IN FEET
 0 25 60



NOTE:

DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR
 UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO
 ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO
 EXCAVATION OR CONSTRUCTION.

REVISION:	DATE:	REVISED BY:
CORRECT AKA NAME	02/23/06	B.L.
CHANGE PAD SIZE	08/05/05	B.L.
 Daggett Enterprises, Inc. Surveying and Oil Field Services P. O. Box 15068 Farmington, NM 87401 Phone (505) 326-1772 Fax (505) 326-6019 NEW MEXICO L.S. 14831		
DRAWN BY: G.V.	CADFILE: MN428_PL8	
ROW#: MN428	DATE: 06/13/05	