Form 3160-5 (June 2015)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an

FORM APPROVED OMB NO. 1004-0137 Expires: January 31, 2018

5.	Lease Serial No.
	N0G13121862

O.	Il Ilidian, Allottee of Tribe Name
	EASTERN NAVAJO

abandoned wei	EASTÉRN NAVAJO							
SUBMIT IN 1	 If Unit or CA/Agreement, Name and/or No. NMNM135216A 							
Type of Well	er				8. Well Name and No. W LYBROOK UNIT	722H		
Name of Operator ENDURING RESOURCES LL	Contact: LAC C E-Mail: lgranillo@endu				9. API Well No. 30-045-35779-00-X1			
3a. Address 1050 17TH STREET SUITE 2: DENVER, CO 80265		b. Phone No. (in h: 505-636-9	nclude area code) 9743		Field and Pool or Exploratory Area LYBROOK MANCOS W			
4. Location of Well (Footage, Sec., T.	, R., M., or Survey Description)				11. County or Parish, St	ate		
Sec 23 T23N R9W 2556FSL 2 36.212189 N Lat, 107.756119			SAN JUAN COUNTY, NM					
12. CHECK THE AF	PPROPRIATE BOX(ES) TO	INDICATE	NATURE OF	NOTICE,	REPORT, OR OTHE	ER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION							
■ Notice of Intent	☐ Acidize	□ Deeper	1	☐ Product	ion (Start/Resume)	■ Water Shut-Off		
Notice of Intent	☐ Alter Casing			☐ Reclama	ation	■ Well Integrity		
☐ Subsequent Report	☐ Casing Repair	□ New C	onstruction	☐ Recomp	olete	☐ Other		
☐ Final Abandonment Notice ↑	☐ Change Plans	☑ Plug ar	d Abandon	□ Tempor	arily Abandon			
%	☐ Convert to Injection	☐ Plug B	☐ Plug Back ☐ Wa		Disposal			
13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection. P&A SHL PREVIOUSLY SET Enduring Resources is requesting to plug and abandon the surface hole associated to the API #30-045-35779 per procedure and attached wellbore diagram. MIRU cement equipment (no rig is required). Hold pre-job safety meeting. Comply with all NMOCD, BLM safety and environmental regulations. Check casing pressure. Ensure there is no pressure on the well. Remove existing piping on casing valve. Cut-off wellhead. RIH with 2 in. poly pipe to PBTD (9-5/8 float collar). Rig up to pump cement down poly pipe. Pump water to establish rate down poly pipe. Pump Cement Plug 1: 9-5/8 surface casing float collar to surface, 190 Sacks Class G Cement (15.8) 14. 1 hereby certify that the foregoing is true and correct.								
	Electronic Submission #5048 For ENDURING RES ted to AFMSS for processing b	SOURCES	C, sent to the	Farmington	•			
Name (Printed/Typed) LACEY G			TING SPE					
Signature (Electronic S	Submission)	D	ate 02/28/20)20				
	THIS SPACE FOR	FEDERAL	OR STATE (OFFICE U	SE			
Approved By JOE KILLINS		TitlePETROLE!	EUM ENGINEER		Date 03/05/2020			
Conditions of approval, if any, are attache certify that the applicant holds legal or equivalent would entitle the applicant to conduct the conduction of th	oject lease	Office Farmingt						
Title 18 U.S.C. Section 1001 and Title 43	U.S.C. Section 1212, make it a crim	ne for any perso	n knowingly and	willfully to ma	ake to any department or a	gency of the United		

(Instructions on page 2)
** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED **



Additional data for EC transaction #504891 that would not fit on the form

32. Additional remarks, continued


lb/gal, 1.17 cuft/sx, 5.03 gal/sx water, 2% calcium chloride, 50% excess). Establish circulation with cement down 2 in. poly pipe and back to surface. Ensure that good cement is circulated to surface. Cut off casing and poly pipe below grade and install P&A marker to comply with regulations. Record GPS coordinates for P&A marker on EOW report. Photograph P&A marker in place. RDMO cement


WELL: W LYBROOK UNIT 722H

API: 30-045-35779

GL (FT): 6,719 KB (FT): 6,740

KB - GL (FT): 21





RIH W 2" POLY PIPE TO TD CEMENT W/ 190 SX CMT CLASS G, 15.8 PPG, 1.17 CUFT/SX

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT FARMINGTON DISTRICT OFFICE

6251 COLLEGE BLVD. FARMINGTON, NEW MEXICO 87402

Attachment to notice of Intention to Abandon:

Re: Permanent Abandonment

Well: 722Y

CONDITIONS OF APPROVAL

- 1. Plugging operations authorized are subject to the attached "General Requirements for Permanent Abandonment of Wells on Federal and Indian Lease."
- 2. Farmington Office is to be notified at least 24 hours before the plugging operations commence (505) 564-7750.

GENERAL REQUIREMENTS FOR PERMANENT ABANDONMENT OF WELLS ON FEDERAL AND INDIAN LEASES FARMINGTON FIELD OFFICE

- 1.0 The approved plugging plans may contain variances from the following minimum general requirements.
 - 1.1 Modification of the approved plugging procedure is allowed only with the prior approval of the Authorized Officer, Farmington Field Office.
 - 1.2 Requirements may be added to address specific well conditions.
- 2.0 Materials used must be accurately measured. (densometer/scales)
- 3.0 A tank or lined pit must be used for containment of any fluids from the wellbore during plugging operations and all pits are to be fenced with woven wire. These pits will be fenced on three sides and once the rig leaves location, the fourth side will be fenced.
 - 3.1 Pits are not to be used for disposal of any hydrocarbons. If hydrocarbons are present in the pit, the fluids must be removed prior to filling in.
- 4.0 All cement plugs are to be placed through a work string. Cement may be bull-headed down the casing with prior approval. Cement caps on top of bridge plugs or cement retainers may be placed by dump bailer.
 - 4.1 The cement shall be as specified in the approved plugging plan.
 - 4.2 All cement plugs placed inside casing shall have sufficient volume to fill a minimum of 100' of the casing, or annular void(s) between casings, plus an excess volume sufficient to provide for 50 linear feet of fill above the plug.
 - 4.3 Surface plugs may be no less than 50' in length.
 - 4.4 All cement plugs placed to fill annular void(s) between casing and the formation shall be of sufficient volume to fill a minimum of 100' of the annular space plus 100% excess, calculated using the bit size, or 100' of annular capacity, determined from a caliper log, plus an excess volume sufficient to provide for 50 linear feet of fill above the plug.
 - 4.5 All cement plugs placed to fill an open hole shall be of sufficient volume to fill a minimum of 100' of hole, as calculated from a caliper log, plus an excess volume sufficient to provide for 50 linear feet of fill above the plug. In the absence of a caliper log, an excess of 100% shall be required.
 - 4.6 A cement bond log or other accepted cement evaluation tool is required to be run if one had not been previously ran or cement did not circulate to surface during the original casing cementing job or subsequent cementing jobs.

- 5.0 All cement plugs spotted across, or above, any exposed zone(s), when; the wellbore is not full of fluid or the fluid level will not remain static, and in the case of lost circulation or partial returns during cement placement, shall be tested by tagging with the work string.
 - 5.1 The top of any cement plug verified by tagging must be at or above the depth specified in the approved plan, without regard to any excess.
 - 5.2 Testing will not be required for any cement plug that is mechanically contained by use of a bridge plug and/or cement retainer, if casing integrity has been established.
 - 5.3 Any cement plug which is the only isolating medium, for a fresh water interval or a zone containing a prospectively valuable deposit of minerals, shall be tested by tagging.
 - 5.4 If perforations are required below the surface casing shoe, a 30 minute minimum wait time will be required to determine if gas and/or water flows are present. If flow is present, the well will be shut-in for a minimum of one hour and the pressure recorded. Short or long term venting may be necessary to evacuate trapped gas. If only a water flow occurs with no associated gas, shut well in and record the pressures. Contact the Engineer as it may be necessary to change the cement weight and additives.
- 6.0 Before setting any cement plugs the hole needs to be rolled. All wells are to be controlled by means of a fluid that is to be of a weight and consistency necessary to stabilize the wellbore. This fluid shall be left in place as filler between all plugs.
 - 6.1 Drilling mud may be used as the wellbore fluid in open hole plugging operations.
 - 6.2 The wellbore fluid used in cased holes shall be of sufficient weight to balance known pore pressures in all exposed formations.
- 7.0 A blowout preventer and related equipment (BOPE) shall be installed and tested prior to working in a wellbore with any exposed zone(s); (1) that are over pressured, (2) where the pressures are unknown, or (3) known to contain H_2S .
- 8.0 Within 30 days after plugging work is completed, file a Sundry Notice, Subsequent Report of Abandonment (Form 3160-5), five copies, with the Field Manager, Bureau of Land Management, 6251 College Blvd., Suite A, Farmington, NM 87402. The report should show the manner in which the plugging work was carried out, the extent, by depth(s), of cement plugs placed, and the size and location, by depth(s), of casing left in the well. Show date well was plugged.
- 9.0 All permanently abandoned wells are to be marked with a permanent monument as specified in 43 CFR 3162.6(d). Unless otherwise approved.
- 10.0 If this well is located in a Specially Designated Area (SDA), compliance with the appropriate seasonal closure requirements will be necessary.

All of the above are minimum requirements. Failure to comply with the above conditions of approval may result in an assessment for noncompliance and/or a Shut-in Order being issued pursuant to 43 CFR 3163.1. You are further advised that any instructions, orders or decisions issued by the Bureau of Land Management are subject to administrative review pursuant to 43 CFR 3165.3 and appeal pursuant to 43 CFR 3165.4 and 43 CFR 4.700.