

COPY

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. Type of Work <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM18316	
1b. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name ---	
2. Name of Operator Black Hills Gas Resources, Inc.		7. If Unit or CA Agreement, Name and No. ---	
E-mail: lbenally@bhep.com		8. Lease Name and Well No. Many Canyons 29-04-11 34H	
Contact: Lynn Benally		9. API Well No. 30-039-29981	
3a. Address P.O. Box 249 Bloomfield NM 87413	3b. Phone No. (include area code) 505-634-1111	10. Field and Pool, or Exploratory Chozas Mesa East Blanco Pictured Cliffs	
4. Location of Well (Report location clearly and in accordance with any State Requirements.) At surface 1,955' FSL 1,095' FEL NE /4 SE /4 Lat: 36° 44' 15.4" Long: 107° 13' 06.4" At proposed production zone ±1,600' FSL ±700' FWL (NW/4 SW/4)		11. Sec., T., R., M., or Blk. and Survey or Area I Sec. 11 T 29N R 4W New Mexico PM	
14. Distance in miles and direction from nearest town or post office. Well is located approximately 50 miles east of Bloomfield, New Mexico.		12. County or parish Rio Arriba	13. State New Mexico
15. Distance from proposed location to nearest property or lease line, ft. (Also nearest Drig, unit line, if any) Unit= n/a Lease= ±1,095'	16. No. of acres in lease 640.00	17. Spacing Unit dedicated to this well 320' HSEW 320' 5/2 BH	
18. Distance from proposed location to nearest well, drilling, completed or applied for, on this lease, ft. ± 1,300' Carson 29-04-11 2H	19. Proposed depth 4,000' TVD	20. BLM/BIA Bond No. on file NMB000230	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 7,049' GR	22. Approximate date work will start July 31, 2006	23. Estimated duration 45-60 days drlg + completion	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature <i>Kathy L. Schneebeck</i>	Name (Printed/Typed) Kathy L. Schneebeck, 303-820-4480	Date June 27, 2006
Title Permit Agent for Black Hills Gas Resources, Inc.		
Approved by (Signature) <i>[Signature]</i>	Name (Printed/Typed) AFM	Date 5/30/07
Title AFM		
Office FED		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious, or fraudulent statements or representations as to any matter within its jurisdiction.

Submit application for permit on OGD Form 6-103 prior to constructing location (continued on page 2)

NOTIFY AZTEC OCD 24 HRS.
PRIOR TO CASING & CEMENT

NMOCD

DRILLING OPERATIONS AUTHORIZED ARE
SUBJECT TO COMPLIANCE WITH ATTACHED
"GENERAL REQUIREMENTS"

HOLD 0104 FOR DIRECTIONAL SURVEY + BH survey

4/5/07

DISTRICT 1
1625 N. French Dr., Hobbs, N.M. 88240

DISTRICT II
1301 W. Grand Ave., Artesia, N.M. 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT IV
1220 South St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102

Revised June 10, 2003

Submit to Appropriate District Office

State Lease - 4 Copies

Fee Lease -- 3 Copies

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-039-29981	² Pool Code EF 74960	³ Pool Name choza Mesa Pictured Cliffs
⁴ Property Code 36439	⁵ Property Name MANY CANYONS 29-04-11	⁶ Well Number 34H
⁷ OGRID No. 013925	⁸ Operator Name BLACK HILLS GAS RESOURCES	⁹ Elevation 7049'


¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
1	11	29-N	4-W		1955	SOUTH	1095	EAST	RIO ARRIBA

¹¹Bottom Hole Location If Different From Surface

UL or lot no. L	Section 11	Township 29-N	Range 4-W	Lot Idn	Feet from the 1600	North/South line SOUTH	Feet from the 700	East/West line WEST	County RIO ARRIBA
¹² Dedicated Acres 320 320.5/2 320 acres - 8			¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No.		

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION


16	CALC'D CORNER DBL. PROP.	17	OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief
LAT. 36°44'15.4" N (NAD 83) LONG. 107°13'06.4" W (NAD 83)		Signature <u>Kathy L. Schneebeck</u> Printed Name <u>Kathy L. Schneebeck</u> Title <u>Permit Agent for Black Hills</u> Date <u>June 27, 2006</u>	
CALC'D CORNER DBL. PROP.		18 SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.	
CALC'D CORNER DBL. PROP.		Date <u>June 27, 2006</u> Signature of Registered Professional Surveyor <u>[Signature]</u>  Certificate Number _____	

WELL PAD DIAGRAM

COMPANY: BLACK HILLS RESOURCES
 LEASE: MANY CANYONS 29-04-11 No. 34H
 FOOTAGE: 1955 FSL, 1095 FEL
 SEC.: 11, TWN: 29-N, RNG: 4-W, NMPM
 ELEVATION: 7049'




SCALE IN FEET
 0 25 50



NOTE:

DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO EXCAVATION OR CONSTRUCTION.

REVISION:	DATE:	REVISED BY:
CHANGE RESERVE PIT	06/20/06	B.L.
CHANGE ACCESS LENGTH	10/24/05	B.L.
 Daggett Enterprises, Inc. Surveying and Oil Field Services P. O. Box 15068 • Farmington, NM 87401 Phone (505) 326-1772 • Fax (505) 326-6019 NEW MEXICO L.S. 14831		
DRAWN BY: B.L.	CADFILE: MN395PL8	
ROW#: MN395	DATE: 06/22/05	

WELL-PAD CROSS-SECTIONAL DIAGRAM


COMPANY: BLACK HILLS GAS RESOURCES
 LEASE: MANY CANYONS 29-04-11 No. 34H
 FOOTAGE: 1955 FSL, 1095 FEL
 SEC.: 11, TWN: 29-N, RNG: 4-W, NMPM
 ELEVATION: 7049'

NOTE:

DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR
 UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO
 ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO
 EXCAVATION OR CONSTRUCTION.


ELEV. A-A'

C/L




ELEV. B-B'


C/L



ELEV. C-C'

C/L



REVISION:	DATE:	REVISION BY:	DATE:
	10/12/05	B. LEIDY	
CHANGE PAD SIZE			
Daggett Enterprises, Inc. Surveying and Oil Field Services P. O. Box 15068 • Farmington, NM 87401 Phone (505) 326-1772 • Fax (505) 326-6019 NEW MEXICO L.S. 14831 COPY: MN395CFB DATE: 06/22/05			
DRAWN BY: B.L. ROW: MN395			

Black Hills Gas Resources, Inc.
Many Canyons 29-04-11 34H
Surface: 1,955' FSL 1,095' FEL (NE/4 SE/4)
BHL: ±1,600' FSL ±700' FWL (NW/4 SW/4)
Sec. 11 T29N R4W
Rio Arriba County, New Mexico
Federal Lease: NMNM18316

DRILLING PROGRAM

This Application for Permit to Drill (APD) is filed under the Notice of Staking (NOS) process as stated in Onshore Order No. 1 and supporting Bureau of Land Management (BLM) documents. This NOS process included an on-site meeting on September 22, 2005, prior to the submittal of the application, at which time the specific concerns of Black Hills Gas Resources, Inc. (Black Hills) and the United States Forest Service – Jicarilla Ranger District (USFS) were discussed. USFS is the Surface Management Agency (SMA) for this wellpad and access road. All specific concerns of the USFS representatives are addressed herein, as are specific stipulations from the BLM.

This is a new vertical and horizontal well to be drilled into the Pictured Cliffs formation. See also the attached Horizontal Drilling Program.

SURFACE FORMATION – San Jose

GROUND ELEVATION – 7,049'

ESTIMATED FORMATION TOPS - (Water, oil, gas and/or other mineral-bearing formations)

San Jose	Surface	Sandstone, shales & siltstones
Nacimiento	2,360'	Sandstone, shales & siltstones
Ojo Alamo	3,435'	Sandstone, shales & siltstones
Kirkland	3,450'	Sandstone, shales & siltstones
Fruitland Coal	3,640'	Sandstone, shales & siltstones
Pictured Cliffs	3,732'	Sandstone, shales & siltstones
TOTAL DEPTH	4,000'	TVD
	7,040.00'	MD (length of horizontal section)

Estimated depths of anticipated fresh water, oil, or gas:

Tertiary

San Jose	surface	Gas
Nacimiento	2,360'	Gas
Ojo Alamo	3,435'	Gas
Fruitland Coal	3,640'	Gas
Pictured Cliffs	3,732'	Gas

HORIZONTAL DRILLING PROGRAM

- A) Kick Off Point is estimated to be at $\pm 3,252'$ TVD
 B) 5-1/2" casing will be set to 4,000' in the vertical portion of the well. After the casing is set vertically, a window will be milled out at the Kick Off Point, the horizontal portion of the well will be drilled and a liner will run the distance of the horizontal hole.

CASING PROGRAM

Depth	Hole Diameter	Casing Diameter	Casing Weight and Grade	Cement
0' – 250' TVD	12-1/4"	8-5/8"	J-55 24# ST&C New	To surface (± 175 sxs Standard Cement containing 2% CaCl ₂ and 0.25 lb/sx LCM) **
0' – 4,000 TVD'	7-7/8"	5-1/2"	J-55 15.5# LT&C New	TD to surface (Lead: ± 300 sxs Lite Standard Cement. Tail: 400 sxs 50:50 POZ containing 0.25 lb/sx LCM)* **
3,252' TVD (KOP) – End of Lateral Bore	4-3/4"	2-7/8"	PH-6 (Liner)	None

* Actual cement volume to be determined by caliper log.

** Cement will be circulated to surface.

Yields:

Surface: Standard Cement yield: = $1.2 \text{ ft}^3/\text{sx}$ (mixed at 15.6 lb/gal)

Production: Lite Standard Cement yield: = $1.59 \text{ ft}^3/\text{sx}$ (mixed at 13.4 lb/gal)
 50:50 POZ yield = $1.27 \text{ ft}^3/\text{sx}$ (mixed at 14.15 lb/gal)

All fresh water and prospectively valuable minerals encountered during drilling, will be recorded by depth and protected.

PRESSURE CONTROL

BOPs and choke manifold will be installed and pressure tested before drilling out under surface casing (subsequent pressure test will be performed whenever pressure seals are broken), and then will be checked daily as to mechanical operating condition. BOP's will be pressure tested at least once every 30 days. Ram type preventors and related pressure control equipment will be pressure tested to 1,000 psi. Annular type preventor will be pressure tested to 50% of the rated working pressure, not to exceed 1,000 psi. All casing strings will be pressure tested to 0.22 psi/ft. or 1,000 psi, whichever is greater, not to exceed 70% of internal yield.

BOP to be either double gate rams or an annular preventor as per Onshore Order No. 2.

Statement on Accumulator System and Location of Hydraulic Controls

The drilling rig has not yet been selected for this well. Selection will take place after approval of this application. Manual and/or hydraulic controls will be in compliance with Onshore Order No. 2 for 2M systems.

A remote accumulator will be used. Pressures, capacities, location of remote hydraulic and manual controls will be identified at the time of the BLM supervised BOP test.

MUD PROGRAM

0' - 300' Fresh water - M.W. 8.5 ppg, Vis 30-33
250 300' - TD' Clean Faze - Low solids non-dispersed
M.W.: 8.5 - 9.2 ppg
Vis.: 28 - 50 sec
W.L.: 15cc or less

Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kick" will be available at wellsite.

AUXILIARY EQUIPMENT

- A) A Kelly cock will be kept in the drill string at all times
- B) Inside BOP or stab-in valve (available on rig floor)
- C) Mud monitoring will be visually observed

LOGGING, CORING, TESTING PROGRAM

- A) Logging: DIL-CNL-FDC-GR - TD - BSC (GR to surface)
Sonic (BSC to TD)
- B) Coring: None
- C) Testing: Possible DST - None anticipated. Drill stem tests may be run on shows of interest

ABNORMAL CONDITIONS

- A) Pressures: No abnormal conditions are anticipated
Bottom hole pressure gradient - 0.31 psi/ft
- B) Temperatures: No abnormal conditions are anticipated
- C) H₂S: See H₂S Plan if H₂S is encountered.
- D) Estimated bottomhole pressure: 1,240 psi


ANTICIPATED START DATE

July 24, 2006

COMPLETION

The location pad will be of sufficient size to accommodate all completion activities and equipment. A string of 2-7/8" PH-6 tubing will be run for a flowing string. A Sundry Notice will be submitted with a revised completion program if warranted.


Job Number: 205-xxx
Company: BHEP
Lease/Well: Many Canyons 29-04-11 #34H
Location: Rio Arriba CO., NM



2-M SYSTEM

Black Hills Gas Resources, Inc.

ANNULAR PREVENTOR MAY BE SUBSTITUTED FOR DOUBLE GATE PREVENTORS
BOP PRESSURE TEST TO 1,000 PSI



Hydrogen Sulfide Drilling Operations Plan

I. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H_2S).
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H_2S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H_2S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H_2S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H_2S zone (within 3 days or 500 feet) and weekly H_2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H_2S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

II. H_2S Safety Equipment and Systems

Note: All H_2S safety equipment and systems, if necessary, will be installed, tested, and operational when drilling reaches a depth of 500 feet above or three days prior to penetrating the first zone containing or reasonably expected to contain H_2S .

A. Well control equipment:

1. Choke manifold with a minimum of one remote choke.
2. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.

Black Hills Gas Resources, Inc.

B. Protective equipment for essential personnel:

1. Mark II Surviveair 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

C. H₂S detection and monitoring equipment:

1. Two portable H₂S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H₂S levels of 10 ppm are reached.

D. Visual warning systems:

1. Wind direction indicators as shown on well site diagram.
2. Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used when appropriate. See example attached.

E. Mud program:

1. The mud program has been designed to minimize the volume of H₂S circulated to the surface. Proper mud weight, safe drilling practices, and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

F. Metallurgy:

1. All drill strings, casings, tubing, wellhead, blowout preventors, drilling spools, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
2. All elastomers used for packing and seals shall be H₂S trim.

G. Communication:

1. Cellular telephone communications in company vehicles.

H. Well testing:

1. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill stem testing operations conducted in an H₂S environment will use the closed chamber method of testing.