A COMPLETE C-144 MUST BE SUBMITTED TO AND APPROVED BY THE NMOCD FOR: A PIT, CLOSED LOOP SYSTEM, BELOW GRADE TANK, OR PROPOSED ALTERNATIVE METHOD, PURSUANT TO NMOCD PART 19.15.17, PRIOR TO THE USE OR CONSTRUCTION OF THE ABOVE APPLICATIONS

RECEIVED

RCVD MAY 20 '09 MIL CONS. DIV. DIST. 3

APR 13 200

Bureau of Land Managémbase Serial No.

FORM APPROVED OMB NO. 1004-0137

MDA 701-98-00 13, Tract 4

Expires: March 31,2007

UNITED STATES

DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

Form 3100-3

(April 2004)

APPLICATION FOR PERMIT TO DRILL OR REENTER

Farmington Field Office 6. If Indian, Allottee or Tribe Name

74 1 2107(1101(1101(1101)) 10		OIT ILLEIT I EIT	1	,	
				Jicarilla Ap	ache
			7	. If Unit or CA Agreement,	Name and No.
1a. Type of Work: X DRILL	REEN	TER	-	T N 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
1b. Type of Well: Oil Well X Gas Well Other Single Zone Multiple Zone			1 -	. Lease Name and Well No.	
		Jicarilla 29-02-	23 #121		
2. Name of Operator			۱۶		
Black Hills Gas Resources				30-039-30747	
3a. Address 3b. Phone No. (include area code)			10	10. Field and Pool, or Exploratory	
P.O. 249 [505] 634-1111				La Jara Canyon Tertiary	
	Bloomfield, NM 87413			11. Sec., T., R., M., or Blk, And Survey or Area	
At surface	c ,,,,,,,,	, state toquit ements. ,	1.	500., 1., 10, 112, 01 220 1	
1,775' FNL 950' FWL SW/NW Unit E				Sec. 23 T29N	R02W
At proposed prod. zone		. 500.25	20211		
14. Distance in miles and direction from the nearest town or pos	13	2. County or Parish	13. State		
				Rio Arriba	NM
25 Miles southwest from Dulce, New Mexico					_L
15. Distance from proposed* location to nearest		16. No. of acres in lease	17. Spacu	ng Unit dedicated to this wel	ll .
property or lease line, ft. Approx. 1,	200'	Approx. 9,600 acres		160 ACRES	NINIL
(Also to nearest drlg. unit line, if any)				10011-01-01	4444
18. Distance from proposed location*		19. Proposed Depth	20. BLM/	BIA Bond No. on file	
to nearest well, drilling, completed, Approx. ±6	,00 0,	±2,000 TVD		BIA - MMSP02670	675
applied for, on this lease, ft.					
21. Elevations (Show whether DF. RT, GR, etc.)		22. Aproximate date work will	start*	23. Estimated duration	
7,236' GR		Apr-09		45-60 Days drill + completion	
		24. Attachments			
The following, completed in accordance with the requirements o	f Onshore	e Oil and Gas Order No. 1 shall b	e attached	to this form:	
		•			
1. Well plat certified by a registered surveyor. 4. Bond to cover the operation			perations	unless covered by existing be	ond on file(see
2. A Drilling Plan. item 20 above).					
 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). 5. Operator certification. 6. Such other site specific in 				nation and/ or plans as may l	he required by the a
0010 shan be med with the appropriate 1 order between 351		authorized officer.			
25. Signature	Name	(Printed/ Typed)		Date /	
lariel Mouve	,	I I	Daniel Ma		13-119
Title Control of the	ш				001
Regulatory Technician (
Approved By (Signature)	Name	(Printed/ Typed)		Date/	10/20
MI Illanlee wood				5//	9/09
Title ATA	Office	T-T-			
· M	1	100			

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to co operations thereon.

Conditions of approval, if any, are attached

fitte 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the Unite States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

* (Instructions of Adge 4) AZIEC OCD 24 HI13. PRIOR TO CASING & CEMENTOCO H2S POTENTIAL EXIST

BLM'S APPROVAL OR ACCEPTANCE OF THIS ACTION DOES NOT RELIEVE THE LESSEE AND OPERATOR FROM OBTAINING ANY OTHER **AUTHORIZATION REQUIRED FOR OPERATIONS** ON FEDERAL AND INDIAN LANDS

DISTRICT 1 1625 N. Prench Dr., Hobbs, N.M. 88240

State of New Mexico Energy, Minerals & Natural Resources Department

Form C-102 Revised October 12, 2005

DISTRICT II 1301 W. Grand Ave., Artesia, N.M. 88210

OIL CONSERVATION DIVISIONAPR I Submit to Appropriate District Office 1220 South St. Francis Dr.
Santa Fe, NM 87505 Bureau of Land Management

DISTRICT III 1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT IV 1220 South St. Francis Dr., Santa Fe, NM 87505 Farmington Field Office AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

30.039.30	747	*Pool Code 97036	² Pool Name LA JARA CANYON	TERTIARY
Property Code	1	Property Name JICARILLA 29-02-23		• Well Number
OGRID No	*Operator Name		• Elevation	
013925	BLACK HILLS GAS RESOURCES		7236	

10 Surface Location UL or lot no. Section North/South line Township Range Lot Idn Feel from the Feet from the East/West line County Ε 23 29-N 1775 NORTH WEST RIO ARRIBA 2-W 950 " Bottom Hole Location If Different From Surface County UL or lot no. Section Township Feet from the North/South line Feet from the Dedicated Acres ¹⁹ Joint or Infill H Consolidation Code *Order No. 160 - NW/4

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED

16	OR A NON-STANDARD UNIT HAS BEE	
FD. MK'D. STONE W/ P&C STAMPED L.S. ND. 8894	S 88-23-46 W 5118.50' (M) FD. MK'D. W/ P&C S L.S. NO	
N 1-33-26" E 5090.37" (M)	LAT: 36.71273' N. (NAD 83) LONG; 107.01794' W. (NAD 83)	Signature Datie Daviel Marie 18 SURVEYOR CERTIFICATION I hereby certify that the well acastem shown on this pic was platted from field noise of actual surveyer trade by me or under my supervision, and that the same is true and correct to the heit of my belief. MARCH 20 2006
FD. MK'D. STONE W/ P&C STAMPED L.S. NO. 8894		Date of State A Resident Surveyor. Signature and ME Age. Signature and ME Age. Certificate in SEAS SIGNAT.



RECEIVED

Jicarilla 29-02-23 #121

Surface Location: 1,775' FNL 950' FWL (SW/NW) Unit E

Sec.23 T29N R2W

Rio Arriba County, New Mexico Lease: Contract MDA 701-98-0013, Tract 4 MAY 0 4 2009

Bureau of Land Management Farmington Field Office

DRILLING PROGRAM

(Per Rule 320)

This Application for Permit to Drill (APD) was initiated under the NOS process as stated in Onshore Order No. 1 and supporting Bureau of Land Management (BLM) documents. This NOS process includes an onsite meeting which was held on October 31, 2006 as determined by Bureau of Indian Affairs (BIA) and Jicarilla Oil & Gas Administration (JOGA) and at which time the specific concerns of Black Hills Gas Resources (BHGR), BIA, and JOGA were discussed.

SURFACE FORMATION – San Jose

GROUND ELEVATION – 7,236'

ESTIMATED FORMATION TOPS - (Water, oil, gas and/or other mineral-bearing formations)

San Jose

Surface

Sandstone, shales & siltstones

Nacimiento

1,929'

Sandstone, shales & siltstones

TOTAL DEPTH

2,019

TVD

San Jose

Estimated depths of anticipated fresh water, oil, or gas: Surface

Gas, water, sand

Nacimiento

1,929

Gas, water, sand

CASING PROGRAM

Depth	Hole Diameter	Casing Diameter	Casing Weight and Grade	Cement
0-250' TVD	11"	7"	J-55 20# ST&C New	To surface (± 175 sxs ClassG) **
0' - TD	6-1/4"	4-1/2"	J-55 10.5# LT&C New	TD to surface (\pm 630 sxs lite or 65:35 poz and \pm 270 sxs 50:50 poz) *

^{*} Actual cement volume to be determined by caliper log.

Yields:

Standard cement yield: = 1.18 ft³/sx (mixed at 15.60 lb/gal) Production: Lite Standard Cement yield: 187 ft³/sx (mixed at 12.4 lb/gal)

 $50:50 \text{ poz yield} = 1.27 \text{ ft}^3/\text{sx} \text{ (mixed at 14.15 lb/gal)}$

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and protected.

^{**} Cement will be circulated to surface

PRESSURE CONTROL

BOPs and choke manifold will be installed and pressure tested before drilling out under surface casing (subsequent pressure test will be performed whenever pressure seals are broken), and then will be checked daily as to mechanical operating condition. BOP's will be pressure tested at least once every 30 days. Ram type preventors and related pressure control equipment will be pressure tested to 1,000 psi. Annular type preventor will be pressure tested to 50% of the rated working pressure, not to exceed 1,000 psi. All casing strings will be pressure tested to 0.22 psi/ft. or 1,500 psi, whichever is greater, not to exceed 70% of internal yield.

BOP to be either double gate rams or an annular preventor as per Onshore Order No. 2.

Statement on Accumulator System and Location of Hydraulic Controls

The drilling rig has not yet been selected for this well. Selection will take place after approval of this application. Manual and/or hydraulic controls will be in compliance with Onshore Order No. 2 for 2M systems.

A remote accumulator will be used. Pressures, capacities, location of remote hydraulic and manual controls will be identified at the time of the BLM supervised BOP test.

MUD PROGRAM

0' - 250' Fresh water – M.W. 8.5 ppg, Vis 30-33
250' - TD' Fresh water- Low solids non-dispersed
M.W. 8.5 – 9.2 ppg
Vis – 28 – 50 sec
W.L. 15cc or less

Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kick" will be available at wellsite.

AUXILIARY EQUIPMENT

- A) A Kelly cock will be kept in the drill string at all times
- B) Inside BOP or stab-in valve (available on rig floor)
- C) Mud monitoring will be visually observed

LOGGING, CORING, TESTING PROGRAM

A) Logging: GR/SP/CAL - Resistivity/Conductivity - Neutron/Density - Bulk Density/RWA

From TD to SC

B) Coring: None

C) Testing: Possible DST – None anticipated. Drill stem tests may be run on shows of interest

ABNORMAL CONDITIONS

A) Pressures: No abnormal conditions are anticipated

Bottom hole pressure gradient - 0.31 psi/ft

B) Temperatures: No abnormal conditions are anticipated

C) H₂S: See attached H₂S plan in event H₂S is encountered.

D) Estimated bottomhole pressure: 682 psi

ANTICIPATED START DATE

May 1, 2009

COMPLETION

The location pad will be of sufficient size to accommodate all completion activities and equipment. The well will be perforated based on log results. The well may be acid stimulated or frac stimulated if needed. A string of 2-3/8" J-55 4.7#/ft tubing will be run for a flowing string. A Sundry Notice will be submitted with a revised completion program if warranted.



Hydrogen Sulfide Drilling Operations Plan

I. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- 1. The hazards and characteristics of hydrogen sulfide (H₂S).
- 2. The proper use and maintenance of personal protective equipment and life support systems.
- 3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- 4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- 1. The effects of H₂S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
- 2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and will control procedures.
- 3. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H_2S zone (within 3 days or 500 feet) and weekly H_2S and will control drills for all personnel in each crew. The initial training sessions shell include a review of the site specific H_2S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will required to carry documentation that they have received the proper training.

II. H2S safety equipment and Systems

Note: All H_2S safety equipment and systems (if necessary) will be in stalled, tested, and operational when drilling reaches a depth of 500 feet above the three days prior to penetrating the first zone containing or reason ably expected to contain H_2S .

A. Well control equipment:

- 1. Choke manifold with a minimum of one remote choke.
- Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- B. Protective equipment for essential personnel

1. Mark II Surniveair 30-minute units located in the doghouse and at briefing areas, as indicated on will site diagram.

C. H₂S detection and monitoring equipment:

Two portable H₂S monitors positioned on location for best coverage and response.
 These units have warning lights and aqudilbesirens when H₂S levels of 10ppm.

D. Visual warning systems:

- 1. Wind direction indicators as shown on well site diagram.
- Caution/Danger signs shall be posted on roads providing direct access to location.
 Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used when appropriate. See example attached.

E. Mud program:

 The mud programs has been designed to minimize the volume of H₂S circulated to the surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

F. Metallurgy:

- 1. All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- All elastomers used for packing and seals shall be H₂S trim.

G. Communication:

1. Cellular telephone communications in company vehicles.

H. Well testing:

 Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity which are necessary to safely and adequately conduct the test. The drill stem lesting will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill stem testing operations conducted in an H₂S environment will use the closed chamber method of testing.

2-M SYSTEM

Black Hills Gas Resources, Inc.

ANNULAR PREVENTOR MAY BE SUBSTITUTED FOR DOUBLE GATE PREVENTORS BOP PRESSURE TEST TO 1,000 PSI

