

UNITED STATES
DEPARTMENT OF INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

SEP 02 2009

FORM APPROVED
Budget Bureau No. 1004-0135
Expires March 31, 1993

SUNDRY NOTICE AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use APPLICATION TO DRILL for permit for such proposals.

5 Lease Designation and Serial No.
NMSF-078764

6 If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation
Rosa Unit

8. Well Name and No
Rosa Unit 183C

9. API Well No.
30-039-30764

10. Field and Pool, or Exploratory Area
BLANCO MV/BASIN DK/BASIN MC

11 County or Parish, State
Rio Arriba, New Mexico

SUBMIT IN TRIPPLICATE

1 Type of Well
Oil Well Gas Well X Other

2. Name of Operator
WILLIAMS PRODUCTION COMPANY

3. Address and Telephone No.
PO Box 640 Aztec, NM 87410-0640

4. Location of Well (Footage, Sec., T, R., M, or Survey Description)
2330' FNL & 305' FEL SEC 19 31N 5W

CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

X Notice of Intent
Subsequent Report
Final Abandonment

TYPE OF ACTION

Abandonment
Recompletion
Plugging Back
Casing Repair
Altering Casing
X Other Casing change
Change of Plans
New Construction
Non-Routine Fracturing
Water Shut-Off
Conversion to Injection
Dispose Water
(Note Report results of multiple completion on Well Completion or Recompletion Report and Log form)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)*

Due to change in plans Williams intends to change the casing design on this well as per attached operation plan

CONDITIONS OF APPROVAL

Adhere to previously issued stipulations

RCVD SEP 5 '09

OIL CONS. DIV.

DIST. 3.

14. I hereby certify that the foregoing is true and correct

Signed Larry Higgins
Larry Higgins

Title Drilling COM Date 9-1-09

(This space for Federal or State office use)

Approved by TL Salyers

Title PE

Date 9/4/09

Conditions of approval, if any:

NMOC



WILLIAMS PRODUCTION COMPANY

Operations Plan

(Note: This procedure will be adjusted on site based upon actual conditions)

DATE: 9/1/2009 **FIELD:** Basin DK/ Basin MC/BlancoMV
WELL NAME: Rosa #183C **SURFACE:** NM G&F/BLM
BH LOCATION: SENE Sec 19-31N-5W
Rio Arriba, NM **MINERALS:** Federal
ELEVATION: 6,327' GR **LEASE #** SF-078764
MEASURED DEPTH: 8,181'

I. GEOLOGY: Surface formation - San Jose

A. FORMATION TOPS: (KB)

Name	MD	Name	MD
Ojo Alamo	2,466	Point Lookout	5,666
Kirtland	2,591	Mancos	5,976
Fruitland	2,991	Gallup	6,986
Pictured Cliffs	3,216	Greenhorn	7,696
Lewis	3,501	Graneros	7,751
Cliff House	5,421	Dakota	7,881
Menefee	5,471	Morrison	8,131
		TD	8,181

- B. MUD LOGGING PROGRAM:** Mudlogger on location from intermediate csg to TD. Mud logger to pick TD.
- C. LOGGING PROGRAM:** HRI/Temp from intermediate casing to TD. SDL\DSN\DSN over zones of interest.
- D. NATURAL GAUGES:** Gauge any noticeable increases in gas flow. Record all gauges in Tour book and on morning reports.

II. DRILLING

- A. MUD PROGRAM:** Use Water + Gel/Polymer sweeps to drill Surface hole. Convert to a LSLD - EZ-MUD system mud (+/-50 Vis.) to drill 9-7/8 in. Intermediate Hole. Increase vis to +/-60 to run Casing. Treat for lost circulation as necessary. Obtain 100% returns prior to cementing. Notify Engineering of any mud losses. Use Air , Air Hammer and 6-3/4 in. Flat btm. bit to drill-out of 7-5/8 in. csg. and to TD well at +/- 8,181 ft. (MD). ✓
- B. BOP TESTING:** While drill pipe is in use, the pipe rams and the blind rams will be function tested once each trip. The anticipated reservoir is expected to be less than 1300 psi, so the BOPE will be tested to **250 psi (Low) for 5 minutes** and **1500 psi (High) for 10 minutes**. Utilize a BOPE Testing Unit with a recording chart and appropriate test plug for testing. The drum brakes will be inspected and tested each tour. **All tests and inspections will be recorded in the tour book as to time and results.**

III. MATERIALS**A. CASING PROGRAM:**

CASING TYPE	OH SIZE (IN)	DEPTH (MD) (FT)	CASING SIZE (IN)	WEIGHT (LB)	GRADE
Surface	14 3/4	300	10 3/4	40.5	K-55
Intermediate	9 7/8	3,691	7 5/8	26.4	K-55
Longstring	6 3/4	8,181	4 1/2	11.6	N-80

B. FLOAT EQUIPMENT:

1. SURFACE CASING: 10 3/4" notched regular pattern guide shoe. Run (1) standard centralizer on each of the bottom (4) joints of Surface Casing.
2. INTERMEDIATE CASING: 7 5/8" cement nose guide shoe with a self-fill insert float. Place float collar one joint above the shoe. Install (1) Turbulent centralizer on each of the bottom (3) joints and one standard centralizer every (3) joints to 2,500 ft. Run (1) Turbulent centralizer at 2,700 ft., 2,500 ft., 2,300ft., 2,000ft., 1,500 ft., and 1,000 ft. (NTL-FRA 90-1).
3. PRODUCTION LINER / CASING: 4-1/2" whirler type cement nose guide shoe with a latch collar on top of 20' bottom joint. Place marker joint above 5,400'. Place centralizers as needed across selected production intervals.

C. CEMENTING:

(Note: Volumes may be adjusted onsite due to actual conditions)

1. SURFACE: Slurry: 290sx (521 cu.ft.) of "Type III" + 2% Cal-Seal 60 + 1/4 # of poly-e-flake/sk + 0.3% Versaset + 2% Econolite + 6% Salt (Yield = 1.796 cu.ft./sk, Weight = 13.5 #/gal.). The 100% excess should circulate cement to the surface. WOC 12 hours. Test csg to 1500psi.
2. INTERMEDIATE: Lead - 525 sx (1430 cu.ft.) of "EXTENDACEM" + 5 #/sk pheno-seal + 5% Cal-Seal 60 (Yield = 2.723 cu.ft./sk, Weight = 11.5 #/gal.). Tail - 100 sx (117.8cu.ft.) of Premium cement + 0.125 #/sk Poly-E-Flake, (Yield = 1.178 cu.ft./sk, Weight = 15.6#/gal.). Total volume = 1548 cu.ft. Bump Plug to 1,500 psi. Notify engineering if cement is not circulated to surface
3. PRODUCTION CASING: 10 bbl Gelled Water spacer. Cement: 610 sx (853 ft³) of "FRACCCEM" + 0.8% Halad-9 + 0.1% CFR-3 + 5 #/sk Gilsonite + 0.125 #/sk Poly-E-Flake + 0.15% HR-800. (Yield = 1.398 ft³/sk, Weight = 13.1 #/gal.). Displace cement at a minimum of 8 BPM. Total volume (853) ft³. WOC 12 hours. ✓

IV. IV COMPLETION**A. CBL**

1. Run Cement Bond Log across all intervals to be perforated and find Top of Cement behind all casing strings if cement not circulated to surface... ✓

B. PRESSURE TEST

1. Pressure test ~~5-1/2"~~ casing to 6000 psi max, hold at 1500 psi for 30 minutes.

4.5"

C. STIMULATION

1. Stimulate Dakota with approximately 10,000# of LiteProp 108™ sand in slick water.
2. Isolate Dakota with a RBP.
3. Perforate Mancos as determined from the open hole logs
4. Stimulate Mancos with 3 stages of approximates 117,000# 40/70 white sand and 7500# 100 mesh white sand
5. Stimulate Point Lookout with approximately 9300# of 14/30 LiteProp™ in slick water.
6. Isolate Point Lookout with a RBP.

7. Perforate the Menefee/Cliff House as determined from the open hole logs.
8. Stimulate with approximately 9300# of 14/30 LiteProp™ in slick water.
9. Test each zone before removing bridge plugs.

D. RUNNING TUBING

1. Production Tubing: Run 2-3/8", 4.7#, J-55, EUE tubing with a SN (1.91" ID) on top of bottom joint. Land tubing in Dakota perforations

Gary Sizemore
Sr. Drilling Engineer