

State of New Mexico
Energy, Minerals and Natural Resources Department
Oil Conservation Division

Sundry Notices and Reports on Wells

<p>1. Type of Well OIL</p> <hr/> <p>2. Name of Operator Geo Engineering</p> <hr/> <p>3. Address & Phone No. of Operator P. O. Box 2966 Santa Fe, NM 87505</p> <hr/> <p>4. Location of Well, Footage, Sec., T, R, M Sec. 20 T-20-N, R-9-W, NMPM, McKinley County Unit O, 490' ^{990' S} FSL and 2300' ^{1280' E} FEL</p>	<p>API # (assigned by OCD) 30-031-05415</p> <p>5. Lease Number Fee</p> <p>6. State Oil & Gas Lease #</p> <p>7. Lease Name/Unit Name Santa Fe Pacific I</p> <p>8. Well No. #10</p> <p>9. Pool Name or Wildcat</p> <p>10. Elevation:</p>
---	--

Type of Submission	Type of Action	
<input checked="" type="checkbox"/> Notice of Intent	<input checked="" type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Other -	

13. Describe Proposed or Completed Operations

A-Plus Well Service, contractor, will plug and abandon said well according to the attached procedure prepared by NMOCD.
This work will be in accordance with State of New Mexico Contract No. 98-521.25-059.

RECEIVED
JAN 22 1998

OIL CON. DIV.

SIGNATURE William F. Clark Contractor DIST. 3 December 30, 1997
William F. Clark

(This space for State Use)
Approved by Johnny Robinson Title DEPUTY OIL & GAS INSPECTOR, DIST. #3 Date JAN 22 1998

COMPANY

Geo Engineering

PROPERTY NAME

Santa Fe Pacific I

WELL NO.

10

DATE

LOCATION (ULSTR)

P-20-20N-09W

FOOTAGE

API NO.


POOL

2 3/8 or 2" Tbg with a galvanized Tee, 2" is two feet above ground level

CASING RECORD:

2 3/8 or 2" Tbg. @ 420'
Calc. T.O.C. @ 344'

0.4
4.3'



344'

8 5/8'
420'
2 3/8 or 2''

COMPANY

Geo Engineering

PROPERTY NAME

Santa Fe Pacific I

WELL NO.

10

DATE

LOCATION (ULSTR)

P-20-20N-09W

FOOTAGE

API NO.

POOL


2 3/8 or 2" Tbg with a galvanized Tee. 2" is two feet above ground level

CASING RECORD:

2 3/8 or 2" Tbg. @ 420'

Calc. T.O.C. @ 344'

1. Determine depth of well.
2. If depth is 300' or more continue with procedure. If not move in rig & clean out csg. to 300'
3. Perf. @ 300' + 30' establish circ. to the surf.
4. GIH with slickline & load csg. with cement.
5. POH with slickline & pump down the csg. & circ. cement to the surf.
6. Install Dry hole marker



O.H
434

8 5/8
420'
2 3/8 or 2''