

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED  
BLM

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.

OCT 12 PM 1:47

5. Lease Designation and Serial No.

SF - 078272

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

DUNN 2E

9. API Well No.

3003905096

10. Field and Pool, or Exploratory Area

BASIN DAKOTA

11. County or Parish, State

Rio Arriba, NM

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

BCO, Inc.

3. Address and Telephone No.

135 Grant, Santa Fe, NM 87501 (505) 983-1228

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

660' FSL + 660' FWL  
S 10-T23N-R7W NMPM, 7299 GR

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment

TYPE OF ACTION

☐ Abandonment

☒ Recompletion

☒ Plugging Back

☐ Casing Repair

☐ Altering Casing

☐ Other

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

CERTIFIED RETURN RECEIPT REQUESTED: P 326 823 113

On October 1, 1993, BCO, INC. recieved verbal approval from Wayne Townsend, to recomplete the Dunn 2E and to build a pit of suitable size within the pad area to allow for the recompletion. The well is to be recompleted as follows:

- 1) A cement retainer will be set at 6016' and 30 sx of classs "B" Neat cement will be squeezed into the existing perfs from 6600' to 6620'
- 2) Squeeze holes will be shot at 5840', 5900', 5914', 5816', a cement retainer will be set at 5826' and 50 sx of class "B" neat cement will be squeezed into these holes
- 3) The Gallup formation will be perforated from approximately 5612' to 5739', acid stimulated and hydraulic fractured

The anticipated starting date is October 6, 1993.  
Attachments: Well Bore Diagram

14. I hereby certify that the foregoing is true and correct

Signed

Title

Senior Field Engineer

Date

10-4-93

(This space for Federal or State office use)

Approved by

Title

Conditions of approval, if any:

APPROVED

OCT 13 1993

DISTRICT MANAGER

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*See Instruction on Reverse Side


NMOCD

# DIAGRAMMATIC WELL SKETCH

FEDERAL DUNN N<sup>o</sup> 2-E

BASIN DAKOTA

SW/4 SW/4 SEC 10 T23N R7W NMPM



2/4/93  
N. L. DUNCAN