

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 42-R1424.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. ☐ OIL WELL ☐ GAS WELL ☒ OTHER		5. LEASE DESIGNATION AND SERIAL NO. Tribal #167 Tracts 1272, 273
2. NAME OF OPERATOR Anerade Petroleum Corporation		6. IF INDIAN, ALLOTTEE OR TRIBE NAME & 274 Jicarilla Apache
3. ADDRESS OF OPERATOR Box 1469, Durango, Colorado		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 990' P.M. and 790' P.M., Sec. 11, T-23N, R-3E, Rio Arriba County, New Mexico. Southeast Lindrith Area.		8. FARM OR LEASE NAME J. Apache "I"
14. PERMIT NO.		9. WELL NO. 1
15. ELEVATIONS (Show whether DF, RT, GR, etc.) GR-7219, DF-7220 & GR-7221		10. FIELD AND POOL, OR WILDCAT South Glenco-Pictured C.
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 11, 23N, 3E, M.M., Southeast Lindrith Area
		12. COUNTY OR PARISH Rio Arriba
		13. STATE New Mex.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

PULL OR ALTER CASING

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON*

REPAIR WELL

CHANGE PLANS

(Other)

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

REPAIRING WELL

FRACTURE TREATMENT

ALTERING CASING

SHOOTING OR ACIDIZING

ABANDONMENT*

(Other) Setting 8-5/8" & 4-1/2" Csg. X
(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

6/4/64 - 137' TD: plug 12 1/2" Hole - 3:15 AM 6/4/64.

Set 8-5/8" OD 2 1/2" 8-RT J-55 R-2 MS Csg. Stac New at 136', w/Larkin IF shoe 136' and (1) Centralizer at 131'. Cemented by M. Service, Inc. w/100 Sacks of Reg. Cement w/2% C.C., Pumped Plug to 115' w/2000 Press., Cement circulated. WOC

6/5/64 - Pressured up on 8-5/8" Csg. w/5000 Press. for 1 1/2 hr.. Held OK.

6/8/64 - 3200' TD - 3167' PBD

Run and set 103 Jts. 4 1/2" OD 9.50' 8-RT J-55 R-2 MS Csg. Stac New, Set 3199', w/Larkin Guide Shoe 3199', Float Collar 3167', (4) Centralizers at 3167', 3075', 2984' & 2891', 200' of Scratchers from 3167' to 2967'. Halliburton cemented 4 1/2" csg. w/100 Sacks of Class "C" Cement w/.75 of 14 CFR-2, Pumped 10 bbls. of brine water ahead of cement, followed by 250 Gals. of 10% HSA Acid on top of plug. Pumped plug to 3167', Ann. Press. 2000, max. Press. 7000. Plug down 6:00 AM 6/9/64.

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE Field Clerk

DATE 6/10/64

(This space for Federal or State office use)



APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side



Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.