

TENTATIVE CEMENTING PROGRAMS

Associated Oil & Gas of New Mexico Inc.
Vigil #1
J-1L-12N-6E

Division-approved Plugging Program

Clean out hole to TD (1201').

Fill with cement from TD to 820'.

Set a cement plug from 140'-240'.

Set a surface plug and marker.

Level pits and clean location.

Presumed downhole equipment.

8 5/8" casing @ 617' W/65 sx.

6 5/8" casing @ 879' W/60 sx cir.

All cement will be Class A,B, or C with or without CaCL.