

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas well ☐ other Salt Water Disposal
2. NAME OF OPERATOR
Petro-Lewis Corporation
3. ADDRESS OF OPERATOR
P.O. Box 509, Levelland, Texas 79336
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 430' FNL & 1690' FEL
AT TOP PROD. INTERVAL: 2818'
AT TOTAL DEPTH: 3102'
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☒
(other) ☐

SUBSEQUENT REPORT OF:

- ☐
☐
☐
☐
☐
☐
☐
☐

5. LEASE
NM-28241
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Federal
7. UNIT AGREEMENT NAME
None
8. FARM OR LEASE NAME
Federal Media
9. WELL NO.
#3
10. FIELD OR WILDCAT NAME
Southwest Media
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 22-T19N-R3W
12. COUNTY OR PARISH
Sandoval
13. STATE
N.M.
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
6869' GR

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1-23-78

On 12-23-77, Petro-Lewis Corporation received approval from Jerry Long, USGS, Durango, Colo., to plug and abandon the above well, due to defective casing. This procedure will be conducted in the following manner:

1. Spot 300' of Class "C" cmt. between 3075'-2775', 35 sx.
2. Spot 300' of Class "C" cmt. between 2300'-2000', 35 sx.
3. Spot 10 sx. of Class "C" cmt. inside 4-1/2" csg. at surface.
4. Spot 30' plug between 4-1/2" and 8-5/8" surface with 10 sx. Class "C".
5. Install abandonment marker and restore location.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.


18. I hereby certify that the foregoing is true and correct

SIGNED Born Inley TITLE Sr. Drlg. Foreman DATE 1/23/78

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side



RECEIVED
JAN 25 1978
U. S. GEOLOGICAL SURVEY
DURANGO, COLO.

Official