


UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or entry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals.

SUBMIT IN TRIPLICATE



FORM APPROVED

Budget Bureau No. 1004-0135

Expires March 31, 1993

5. Lease Designation and Serial No.

NMNM-99728

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

28894

8. Well Name and No.

Bois d' Arc Cejita Blanca 33 # 1

9. API Well No.

30-043-20951

10. Field and Pool, or Exploratory

Undesignated Mesaverde

11. County or Parish, State

Sandoval, New Mexico

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other

- ☒ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or recompletion Report and Log Form)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including, estimated date of starting work.
If well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones of pertinent to this work.

11-8-2001 Synergy Operating, LLC spud this well on Thursday, November 8, 2001 with MOTE Drilling, Inc.
11-8-2001 A 12-1/4" Hole was Air drilled to 162 feet. Seven (7) Jts of 8-5/8" 24# J-55 LTC Casing was run to 162 feet GL and cemented with BJ Services through a string of 1" PVC down the annulus. Four Bow Spring Centralizers were run at 161', 117', 73', & 29'.

2 bbls of water was pumped ahead followed by 15 bbls (84 ft³ / 61 Sxs) of Type III Cement mixed at 14.6 ppg. 3 bbls Good Cement was circulated to surface.

The 8-5/8" Casinghead was screwed on the well with a cap.

11-12-2001 Aztec Excavation installed a 6' diameter, 6' deep culvert over the well.

14. I hereby certify that the foregoing is true and correct

Signed: Thomas E. Mullins

Title: Engineering Manager

Date: 11-16-2001

This space for federal or state office use

Approved by: Patricia M. Hecker

Title: Lands and Mineral Resources

Date: NOV 20 2001

Conditions of approval if any

CBL must be run before setting intermediate casing to ensure good cement is behind

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious, or fraudulent statements or representations as to any matter within its jurisdiction