

Article II - B Paragraph 3

Blow out Preventor to be standard 10" Schaeffer Doublegate Hydraulic BOP tested to 5000 psia. Bop tested when leaving rental warehouse and check for efficient operation daily.