

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas ☒ well ☐ other

2. NAME OF OPERATOR  
EL PASO NATURAL GAS CO.

3. ADDRESS OF OPERATOR  
BOX 289, FARMINGTON, NEW MEXICO

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)  
AT SURFACE: 1610'S, 810'E  
AT TOP PROD. INTERVAL:  
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF	<input type="checkbox"/>	<input checked="" type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input checked="" type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other)	<input type="checkbox"/>	<input type="checkbox"/>

5. LEASE  
SF 078915

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME  
Lindrith Unit

8. FARM OR LEASE NAME  
Lindrith Unit

9. WELL NO.  
84

10. FIELD OR WILDCAT NAME  
So. Blanco P.C.

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA  
Sec. 36, T-24-N, R-3-W  
NMPM

12. COUNTY OR PARISH  
Rio Arriba

13. STATE  
New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)  
7178 GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

9/17/78: T.D. 3190'. Ran 102 joints 2 7/8", 6.4# J-55 production casing, 3179' set at 3190'. Cemented with 164 cu. ft. cement. WOC 18 hours.  
Top of cement 2400'.

11/8/78: Tested casing to 4000#, OK. PBTD 3179'. Perforated 3075, 3078, 3082, 3092, 3097, 3102, 3107, 3116, 3120, 3124 with 1 SPZ. Fraced w/46,000# 10/20 sand and 51,000 gal. water. Flushed w/800 gals. water.

Subsurface Safety Valve: Manu. and Type


18. I hereby certify that the foregoing is true and correct

SIGNED D. G. Lisco TITLE Drilling Clerk DATE 1/9/79

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side



RECEIVED  
JAN 12 1979

U. S. GEOLOGICAL SURVEY  
DURANGO, COLO.