

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☐ other **Wildcat**

2. NAME OF OPERATOR
TransOcean Oil, Inc.

3. ADDRESS OF OPERATOR **1700 First City East Bldg.
1111 Fannin, Houston, Texas 77002**

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: **790' FNL & 790' FEL of Sec 31, T24 N, R3W**
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH: **Vertical Well**

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

CHANGE ZONES ☐

ABANDON* ☐

(other) **Set & cmt 5 1/2" Prod. csg.**

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐
☐
☐

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Drld to TD of 7760' on 11/4/77.

Logged and ran SWC on 11/5/77.

On 11/6/77 ran 193 jts 5 1/2" 15.50# & 17# K-55 ST & C csg. Set @ 7754'.

1st stage - cmt w/425 sx cmt (125 sx dips + 300 sx RHC). Plug bumped w/1500# - no bleed back.

2nd stage thru DV tool @ 5782' - 150 sx 50-50 poz w/4% gel, 12 1/2 Gilsonite and 10% salt, followed w/375 sx neat.

3rd stage thru DV tool @ 3334' - 200 sx 50-50 poz w/4% gel, 12 1/2 Gilsonite and 10% salt. Full circ both stages.

Rig released 11/8/77.

Now waiting on completion rig.

Subsurface Safety Valve: Manu. and Type _____

18. I hereby certify that the foregoing is true and correct

SIGNED Walter H. Evans

TITLE **Drilling Clerk**

DATE **November 10, 1977**

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

5. LEASE
NM 28714

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Federal 28714

9. WELL NO.
1

10. FIELD OR WILDCAT NAME
Wildcat


11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 31, T24 N-R3W

12. COUNTY OR PARISH
Rio Arriba

13. STATE
New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
7269' + GL: RKB 13.88'



NOV 24 1977

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud; or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.