



**Southland Royalty Company**

August 16, 1978

United States Geological Survey  
P. O. Box 1809  
Durango, Colorado

Attention: Blowout Preventer Plan

Dear Sir:

All drilling and completion rigs will be equipped with 6" or larger double gate hydraulic blowout preventers and a hydraulic operated closing unit with steel lines.

The preventer is 3000# working pressure and 6000# test.

All crews will be thoroughly trained in the operation of this preventer. The preventer will be tested frequently enough to insure proper operation.

Yours truly,

L. O. Van Ryan  
District Production Manager

LOVR/dg

**RECEIVED**

**AUG 1978**

**U. S. GEOLOGICAL SURVEY  
DURANGO, COLO.**