


(SUBMIT IN TRIPLICATE)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Land Office **Jicarilla Tribal**
Lease No. **119**
Unit _____
INDIAN LAND



SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	SUBSEQUENT REPORT OF WATER SHUT-OFF	<input checked="" type="checkbox"/>
NOTICE OF INTENTION TO CHANGE PLANS	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF	SUBSEQUENT REPORT OF ALTERING CASING	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE	SUBSEQUENT REPORT OF ABANDONMENT	
NOTICE OF INTENTION TO PULL OR ALTER CASING	SUPPLEMENTARY WELL HISTORY	
NOTICE OF INTENTION TO ABANDON WELL		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

Feb. 24, 1964

Well No. **Hoyt 3-5** is located **1850** ft. from **N** line and **1130** ft. from **W** line of sec. **5**

N of Sec. **5** **26 North 4 West** **T11N**
(1/4 Sec. and Sec. No.) (Twp.) (Range) (Meridian)

Tapacito Pictured Cliffs **Rio Arriba** **New Mexico**
(Field) (County or Subdivision) (State or Territory)

RECEIVED

MAR 3 1964


The elevation of the derrick floor above sea level is **7309** ft.
7299 GL.

DETAILS OF WORK

U. S. GEOLOGICAL SURVEY
WASHINGTON, D. C.

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Spud 2/3/64. Drilled 319' of 15" hole. Roamed to 17". Set 12 3/4" casing at 316' KB. cemented with 315 sacks regular with 2% Ca Cl₂. Circulated cement to surface. Plug down 7:30 P.M. 2/10/64. Drilled 11" hole to 2027. Drilled 9 7/8" hole from 2027 to 4315. Ran 7" 23# casing and set at 4314 KB. Cemented with 215 sacks regular with 4% gel. Tailed in with 65 sacks regular with 2% Ca Cl₂. Plug down at 4:00 A.M. 2/19/64 waited on cement 24 hours. Pressured to 1200# held for 30 minutes. Drilled 6 1/4" hole to 6375. Set 4 1/2" liner from 4218 to 6373 KB. Cemented with 220 sacks of 50-50 pos-mix with 4% gel. Bumped plug with 1000# 10:30 A.M. 2/24/64.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company **Consolidated Oil & Gas Inc.**

Address **P.O. Box 2038**

Farmington, New Mexico

By **Thomas H. Boyd, Jr.**

Title **Area Superintendent**