

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPPLICATE*
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 42-R1424.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL ☐ GAS WELL ☒ OTHER ☐		5. LEASE DESIGNATION AND SERIAL NO. Jicarilla Contract 155	
2. NAME OF OPERATOR AMOCO PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME Jicarilla Apache Tribe	
3. ADDRESS OF OPERATOR 501 Airport Drive, Farmington, New Mexico 87401		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1600' FSL & 1100' FKL, Section 31, T-26-N, R-5-W		8. FARM OR LEASE NAME Jicarilla Contract 155	
14. PERMIT NO.		9. WELL NO. 22	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6652' GL, 6666' RDB		10. FIELD AND POOL, OR WILDCAT Basin Dakota	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NE/4 SE/4 Section 31, T-26-N, R-5-W	
		12. COUNTY OR PARISH Rio Arriba	13. STATE New Mexico

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF ☐	PULL OR ALTER CASING ☐	WATER SHUT-OFF ☐	REPAIRING WELL ☐
FRACTURE TREAT ☐	MULTIPLE COMPLETE ☐	FRACTURE TREATMENT ☐	ALTERING CASING ☐
SHOOT OR ACIDIZE ☐	ABANDON* ☐	SHOOTING OR ACIDIZING ☐	ABANDONMENT* ☐
REPAIR WELL ☐	CHANGE PLANS ☐	(Other) Dual Completion ☒	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*



On 9-17-73 moved in a service unit to dually complete the subject well. Set a Model "NC" bridge plug at 7050' and loaded hole with 0.8% KCl water. Spotted 500 gallons 15% HCl. Perforated intervals 5116-5139, 5165-5171, 5187-5194, 5202-5207, 5216-20, 5231-5237 & 5270-5276 with 1 SPF. Sand-water fraced 9-19-73 with 40,000 gallons treated water, 20,000 pounds 10-20 sand and 20,000 pounds 8-12 sand. Dropped 25 balls midway thru frac and injection rate went from 60 BPM at 2200 psi to 30 BPM at 2900 psi. Maximum pressure 2900 and average 2650 psi. AIR 45 BPM. Cleaned out well to bridge plug at 7050'. Drilled and pushed bridge plug to 7400' PBD. On 9-22-73 set a Model "D" packer at 7040'. Landed 2-3/8" tubing in packer with 1-1/4" tubing landing at 7286'.

18. I hereby certify that the foregoing is true and correct
SIGNED J. ARNOLD SNELL TITLE Area Engineer DATE October 26, 1973

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side



Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.