

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

CONTRACT #100

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

JICARILLA APACHE

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

JICARILLA "D"

9. WELL NO.

12

10. FIELD AND POOL, OR WILDCAT

TAPACITO PICTURED CLIFFS

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

SEC. 29, T-26N, R-3W
N.M.P.M.

12. COUNTY OR PARISH

RIO ARriba

13. STATE

NEW MEXICO

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL ☐ GAS ☒ OTHER ☐
WELL WELL

2. NAME OF OPERATOR

SOUTHERN UNION PRODUCTION COMPANY

3. ADDRESS OF OPERATOR

P. O. Box 808, FARMINGTON, NEW MEXICO 87401

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

1640 FT. FROM THE NORTH LINE & 1620 FT. FROM THE WEST LINE.

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

7101 FT. R.K.B.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

PULL OR ALTER CASING

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON*

REPAIR WELL

CHANGE PLANS

(Other)

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

REPAIRING WELL

FRACTURE TREATMENT

ALTERING CASING

SHOOTING OR ACIDIZING

ABANDONMENT*

(Other)

SUPPLEMENTARY HISTORY

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1. DRILLED 7-7/8" HOLE TO T.D. OF 3850 FT. R.K.B. REACHED T.D. 10/6/73.
2. RAN 96 JOINTS OF 4-1/2", 11.60#, K-55 CASING. LANDED AT 3849 FT. R.K.B. 4-1/2" STAGE COLLAR SET AT 2435 FT. R.K.B. CEMENTED 1ST STAGE WITH 420 CU. FT. OF CEMENT. PLUG DOWN AT 1:15 P.M. 10/6/73. CEMENTED 2ND STAGE WITH 750 CU. FT. OF CEMENT. PLUG DOWN AT 2:15 P.M. 10/6/73. CEMENT CIRCULATED TO SURFACE.
3. MOVED IN AND RIGGED UP COMPLETION UNIT ON 10/30/73.
4. RAN 2-3/8", TUBING AND CLEANED OUT TO P.B.T.D. OF 3806 FT. R.K.B.
5. PRESSURE TESTED CASING TO 3000 PSI. TEST OK.
6. RAN CEMENT BOND LOG AND GAMMA-RAY CORRELATION LOG.
7. PERFORATED PICTURED CLIFFS 2 SHOTS/FT. FROM 3765 FT. TO 3796 FT.
8. SAND WATER FRAC PERFORATIONS WITH 50,000# SAND. USED 52,000 GALLONS OF WATER.
9. RAN 114 JOINTS OF 1-1/2", E.U.E., 2.90#, PCW-55 TUBING TO PICTURED CLIFFS. LANDED AT 3748 FT. R.K.B. BAKER MODEL "F" NIPPLE SET AT 3740 FT. R.K.B.
10. WELL COMPLETED 11/1/73.

18. I hereby certify that the foregoing is true and correct

Original signed by

SIGNED Dan R. Collier
DAN R. COLLIER

TITLE OFFICE MANAGER

DATE NOVEMBER 16, 1973

(This space for Federal or State office use)

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE NOV 16 1973

Instructions


General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations, when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; fluid or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

U.S. GOVERNMENT PRINTING OFFICE: 1963-O-685229

647-485



YOUNG & RUBICAM, INC. NEW YORK, N.Y.

1000 P. O. BOX 1000, NEW YORK, N.Y. 10108

1000 P. O. BOX 1000, NEW YORK, N.Y. 10108

1000 P. O. BOX 1000, NEW YORK, N.Y. 10108

1000 P. O. BOX 1000, NEW YORK, N.Y. 10108

1000 P. O. BOX 1000, NEW YORK, N.Y. 10108

1000 P. O. BOX 1000, NEW YORK, N.Y. 10108