

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
Supra Energy Corporation
3. ADDRESS OF OPERATOR
P. O. Box 808, Farmington, New Mexico 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: **810 ft./S, 830 ft./E line.**
AT TOP PROD. INTERVAL: **Same as above.**
AT TOTAL DEPTH: **Same as above**

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF ☐	☒
FRACTURE TREAT ☐	☐
SHOOT OR ACIDIZE ☐	☐
REPAIR WELL ☐	☐
PULL OR ALTER CASING ☐	☐
MULTIPLE COMPLETE ☐	☐
CHANGE ZONES ☐	☐
ABANDON* ☐	☐
(other) _____	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1. Spud 9-7/8" hole at 2:30 A.M. 6/1/79.
2. Drilled 9-7/8" hole to T.D. of 235 ft. R.K.B.
3. Ran 5 joints (211 ft.) of 7-5/8", 20.00 lb., H-40 Ceg. Landed at 225 ft. RKB.
4. Cemented with 140 sacks of class "G" with 2% CaCl and 1/4 lb. Flo-sels per sack. Plug down at 2:30 P.M. 6/1/79. Cement circulated to surface.

Subsurface Safety Valve: Manu. and Type _____

18. I hereby certify that the foregoing is true and correct


SIGNED Kenneth E. Reddy TITLE Superintendent DATE June 5, 1979

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

5. LEASE	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME Contrast No. 101 Jicarilla Apache	
7. UNIT AGREEMENT NAME	
8. FARM OR LEASE NAME Jicarilla #9	
9. WELL NO. 6	
10. FIELD OR WILDCAT NAME Tapacito - Floated Cliffs	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 12, T-28N, R-4W, N.M.P.M.	
12. COUNTY OR PARISH Rio Arriba	13. STATE New Mexico
14. API NO.	
15. ELEVATIONS (SHOW DF, KDB, AND WD) 6529 OL	

(NOTE: Report results of multiple completion or zone change on Form 9-330.)



Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.