

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)Form approved.
Budget Bureau No. 42-R1424.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL ☐ GAS WELL ☐ OTHER ☐		5. LEASE DESIGNATION AND SERIAL NO.
2. NAME OF OPERATOR Shell Oil Company (Rocky Mountain Division Production)		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR 1700 Broadway, Denver, Colorado 80202		7. UNIT AGREEMENT NAME Carson Unit
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1175' FSL and 1665' FSL Sec 13		8. FARM OR LEASE NAME Unit
14. PERMIT NO.		9. WELL NO. 200
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6408 GL		10. FIELD AND POOL, OR WILDCAT Plati Field
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SW/4 SE/4 Section 13- T 25N-R 12W
		12. COUNTY OR PARISH San Juan
		13. STATE New Mexico

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

As per attached plugging prognosis


Please forward (2) approved copies to:

Oil and Gas Conservation Commission
1100 Alameda Road
Albuquerque, New Mexico 87106

Attention Mr. E. C. Arnold, Supvr. of Oil & Gas

DEC 13 1973

U. S. GEOLOGICAL SURVEY



18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE

DATE


(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:



PLUGGING AND ABANDONING PROGNOSIS
CARSON UNIT 34N-13 (#200)
Sec. 13, T25N, R12W
BISTI FIELD, SAN JUAN COUNTY, NEW MEXICO

PERTINENT DATA:

Elev: 6408'
KB-GL: 11'
TD: 1330'
PBSD: 1283'

Perfs: 1234'-1256'
Shell's W.I.: 100%
AFE: 588770


CURRENT STATUS: Shut in

PROCEDURE:

1. MI and R.U. pulling unit. Pick up a minimum of 1300-ft of available 2" tubing.
2. Check wellhead pressure and bleed off if any, then load well with 21 bbls of water (hole may not stand full).
3. R.U. cementers, and run in hole w/tubing open ended and set a bottom plug from approximately 1100' to TD w/ min. 20 sacks API class A cement w/2% CaCl_2 .
4. Wait a min. of 3 hours before filling the hole w/water. Meanwhile pull tubing and remove wellhead.
5. Spot a top plug from 100' to surface w/10 sacks cement as above.
6. R.D. cementers and pulling unit.
7. Cut off casing 5' below the surface and weld on a casing cap and erect a permanent marker.

 SPC:psl

10/11/73


B. L. Faulk

Div. O.E. K. R. Jordan

Div. P.E. F. A. Wise



Carson Unit 34X-13 (#200)

8 5/8" @ 326'

Calc. Cement top
@ $\approx$ 500 ft. Do
Not Attempt to
Recover Pipe.

Pictured Cliffs
Perfs 1234'-56'

4 1/2" @ 1324'

PB 1283'

TD 1330'



10/10/13
SFC