

submitted in lieu of Form 3160-5

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Sundry Notices and Reports on Wells

200 JUN 25 PM 2:24

1. Type of Well
GAS

2. Name of Operator

**BURLINGTON
RESOURCES**

OIL & GAS COMPANY

3. Address & Phone No. of Operator

PO Box 4289, Farmington, NM 87499 (505) 326-9700

4. Location of Well, Footage, Sec., T, R, M

800' FNL 840' FEL Sec. 20, T-27-N, R-5-W, NMPM

0517 Lease Number

SF-079392

6. If Indian, All. or
Tribe Name

7. Unit Agreement Name

San Juan 27-5 Unit

8. Well Name & Number

SAN JUAN 27-5 UNIT #37

9. API Well No.


300390701900

10. Field and Pool

Tapacito PC/Blanco MV

11. County and State

Rio Arriba Co, NM



12. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OTHER DATA

Type of Submission

Type of Action

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> Notice of Intent | <input type="checkbox"/> Abandonment | <input type="checkbox"/> Change of Plans |
| <input type="checkbox"/> Subsequent Report | <input type="checkbox"/> Recompletion | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Final Abandonment | <input type="checkbox"/> Plugging Back | <input type="checkbox"/> Non-Routine Fracturing |
| | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Water Shut off |
| | <input type="checkbox"/> Altering Casing | <input type="checkbox"/> Conversion to Injection |
| | <input checked="" type="checkbox"/> Other - Re-Stimulation | |

13. Describe Proposed or Completed Operations

1. Pull 2 3/8" tbg.
2. Set CIBP above Mesa Verde perforations.
3. Set RBP above Pictured Cliffs perforations.
4. Pressure test casing.
5. Retrieve RBP above Pictured Cliffs perforations.
6. Run packer and frac string. Set packer above Pictured Cliffs perforations.
7. Acidize and fracture stimulate Pictured Cliffs formation.
8. Clean out wellbore.
9. Run 2-3/8", 4.70#, J-55, EUE tubing and set @ approximately 5536'.
10. Return well to production.

14. I hereby certify that the foregoing is true and correct.

Signed *Reggie Cal* Title Regulatory Administrator Date 1/6/00

(This space for Federal or State Office use)

APPROVED BY *Chip Hamaden* Title Acting Team Lead Date 1/31/00
CONDITION OF APPROVAL, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

NMOCD

San Juan 27-5 Unit #37

Tapacito Pictured Cliffs / Blanco Mesaverde

Unit A, Section 20, T27N, R5W

Rio Arriba County, NM

Elevation: 6491' GL, 6501' KB

LAT: 36° 33.83' / LONG: 107° 22.51'

Current

Proposed

10-3/4", 32.75# SW, csg
set @ 173' w/150 sx
circ to surf

Pictured Cliffs:

Original: Perf'd 3270'-3330'
Frac'd w/33,500 gal wtr,
30,000# sand

7-5/8", 26.40#, J-55 csg
set @ 3445' w/250 sx
TOC @ 2540' (Temp.)

Mesaverde:

Original: Perf'd 4914'-5532'

5-1/2", 15.50#, J-55 csg
set @ 3418'-5617' w/300 sx
TOC @ 3418' (Temp.)

TD: 5621'
PBSD: 5569'

Ojo Alamo @ 2648'

Fruitland @ 3046'

Pictured Cliffs @ 3262'

Cliff House @ 4910'

2-3/8", 4.7#, J-55
tbg set @ 5536'
(182 jts)

Point Lookout @ 5363'

Pictured Cliffs:

Restimulation: Foam Frac
existing perms w/ 175,000#
20/40 sand

2-3/8", 4.7#, J-55
tbg set @ +/- 5536'

TD: 5621'
PBSD: 5569'