

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Sundry Notices and Reports on Wells

SF-080673

1. Type of Well

GAS

2. Name of Operator

MERIDIAN OIL

3. Address & Phone No. of Operator

PO Box 4289, Farmington, NM 87499 (505) 326-9700

4. Location of Well, Footage, Sec., T, R, M

915' FNL, 1020' FEL, Sec. 5, T-27-N, R-4-W, NMPM

5. Lease Number

SF-08673

6. If Indian, All. or Tribe Name

7. Unit Agreement Name

San Juan 27-4 Unit

8. Well Name & Number

San Juan 27-4 U #19

9. API Well No.

30-039-07206

10. Field and Pool

Tapacito Pictured Cliffs
Blanco Mesaverde

11. County and State

Rio Arriba Co, NM

12. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OTHER DATA

Type of Submission

Type of Action

☒ Notice of Intent☐ Abandonment☐ Change of Plans☐ Subsequent Report☐ Recompletion☐ New Construction☐ Final Abandonment☐ Plugging Back☐ Non-Routine Fracturing☐ Casing Repair☐ Water Shut off☐ Altering Casing☐ Conversion to Injection☒ Other - Pay add

13. Describe Proposed or Completed Operations

It is intended to add pay in the Cliff House and Menefee intervals according to the following procedure:

TOOH w/Pictured Cliffs and Mesaverde tubing. Set retrievable bridge plug above the Point Lookout perforations. Perforate and fracture treat the Cliff House and Menefee intervals in one stage. Clean out all intervals and test potential. Rerun Pictured Cliffs and Mesaverde tubing. Return the well to production.

14. I hereby certify that the foregoing is true and correct.

Signed [Signature] (LLL9) Title Regulatory Administrator Date 2/5/96

(This space for Federal or State Office use)

APPROVED BY _____ Title _____ Date _____

CONDITION OF APPROVAL, if any:

APPROVED

FEB 08 1996

DISTRICT MANAGER

NMOCD

San Juan 27-4 Unit #19
Unit A, Sec 5, T-27-N, R-4-W

<u>Location:</u>	915' FNL, 1020' FEL Rio Arriba County, NM	<u>Latitude:</u>	36-36-24
		<u>Longitude:</u>	107-16-3

<u>Current Field:</u>	Blanco MV / Tapacito PC	<u>Completed:</u>	10/27/58
<u>Spud:</u>	6/26/58	<u>Elev KB:</u>	7173'
<u>Elev GL:</u>	7163'	<u>PBTD:</u>	6405'
<u>TD:</u>	6455'		

CASING RECORD:

<u>Hole Size</u>	<u>Casing Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Depth Set</u>	<u>Cmt Vol</u>	<u>Cmt Top</u>
13-1/2"	10-3/4"	32.75#	Armco SW	293'	200 sks	Surf
9-7/8"	7-5/8"	26.4#	J-55	4262'	200 sks	3950'

LINER RECORD:

<u>Hole Size</u>	<u>Casing Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Depth Set</u>	<u>Cmt Vol</u>	<u>Cmt Top</u>
6-3/4"	5-1/2"	15.5#	J-55	4222' - 6450'	300 sks	4550'

TUBING RECORD:

<u>Tubing Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Depth Set</u>	<u>Joints</u>	<u>Other</u>	<u>Depth</u>
2"	4.7#	EUE	6344'	204		
1-1/4"	1.47#	EUE	4096'	130		
					Bkr Mdl D Pkr	4201'

FORMATION TOPS:

Ojo Alamo	3585'	Cliffhouse	5840'
Kirtland	3692'	Menefee	5925'
Fruitland	3874'	Pt Lookout	6205'
Pictured Cliffs	4073'	Gallup	
Lewis	4170'	Dakota	

Logs Run: ES, GRN, GR, IND, ML, TS

Completions: Mesaverde - Point Lookout
6230-46, 6260-76, 6284-6310,
6336-52, 6370-88 (2 spf)
60,000# sand, 190 balls, and
50,000 gal water

Pictured Cliffs
4074-4100, 4114-30, 4142-58 (2
spf)
50,000# sand, 75 balls, and
45,500 gal water

Workover History:

SAN JUAN 27-4 UNIT #19

Unit A, Section 5, T-27-N, R-4-W
Lat. 36-36-24, Long. 107-16-3

CURRENT WELLBORE SCHEMATIC

