

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)


1. oil ☐ gas ☒ other ☐
2. NAME OF OPERATOR
El Paso Natural Gas Company
3. ADDRESS OF OPERATOR
Box 289, Farmington, New Mexico 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
2010'N, 1690'E
AT SURFACE:
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:



(NOTE: Report results of multiple completion or zone change on Form 9-330.)

5. LEASE
SF 080675
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
San Juan 27-4 Unit
8. FARM OR LEASE NAME
San Juan 27-4 Unit
9. WELL NO.
101 (DM)
10. FIELD OR WILDCAT NAME
Basin Dakota, & Blanco MV
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 28, T-27-N, R-4-W N.M.P.M.
12. COUNTY OR PARISH
Rio Arriba
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
7101' GL

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

4-23-80: PBD 8462'. Tested casing to 4000#, OK. Perfed Dakota 8168, 8172, 8176, 8180, 8184, 8195, 8200, 8204, 8208, 8212, 8215, 8220, 8274, 8299, 8303, 8307, 8310, 8374, 8379' w/1 SPZ. Fraced w/156,000# 20/40 sand, 120,000 gal. wtr. Flushed w/17,460 gal. wtr.
4-25-80: Perfed C.H. & Men. 5662, 5668, 5682, 5728, 5750, 5756, 5772, 5778, 5784, 5790' W/1 SPZ. Fraced w/ 31,000# 20/40 sand, 62,000 gal. wtr. Flushed w/ 15,792 gal. wtr. Perfed P.L. 6137, 6142, 6147, 6152, 6160, 6164, 6187, 6194, 6205, 6210, 6221, 6226, 6247, 6263, 6278, 6341, 6351, 6381, 6437, 6444, 6493' W/1 SPZ. Fraced w/73,000# 20/40 sand, 146,000 gal. wtr. Flushed w/16,506 gal. wtr.

Subsurface Safety Valve: Manu. and Type _____

Set @ _____

18. I hereby certify that the foregoing is true and correct

SIGNED D. P. Bisco TITLE Drilling Clerk DATE May 1, 1980

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

MAY 5 1980

*See Instructions on Reverse Side

NMOCO

BY McL Kuchera