

UNITED STATES DEPARTMENT OF THE INTERIOR GEOLOGICAL SURVEY

SUBMIT IN TRIPPLICATE (Other instructions on reverse side)

Form approved. Budget Bureau No. 42-R1424.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT" for such proposals.)

5. LEASE DESIGNATION AND SERIAL NO. NM-0560415
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME Companero
9. WELL NO. #2
10. FIELD AND POOL, OR WILDCAT Blanco MV Tapacitos PC
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 12, T27N, R4W
12. COUNTY OR PARISH Rio Arriba
13. STATE New Mexico

1. OIL WELL [] GAS WELL [X] OTHER

2. NAME OF OPERATOR Southland Royalty Company

3. ADDRESS OF OPERATOR P. O. Drawer 570, Farmington, NM 87401

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 810' FSL & 1830' TEL

14. PERMIT NO. 15. ELEVATIONS (Show whether DF, ST, GR, etc.) 7149' GR

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF [] PULL OR ALTER CASING []
FRACTURE TREAT [] MULTIPLE COMPLETE []
SHOOT OR ACIDIZE [] ABANDON* []
REPAIR WELL [] CHANGE PLANS []
(Other) []

SUBSEQUENT REPORT OF:

WATER SHUT-OFF [] REPAIRING WELL []
FRACTURE TREATMENT [] ALTERING CASING []
SHOOTING OR ACIDIZING [] ABANDONMENT* []
(Other) Perforation and Stimulation [XX]


(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

9-14-79 Perforated the Mesa Verde at 5874', 5879', 5884', 5892', 5896', 6211', 6218', 6223', 6278', 6283', 6313', 6320', 6351'. Total of 13 holes. Brokedown with 1000 gallons of 15% HCl and 20 balls. Frac'd with 76,000 gallons of water and 71,000# of 20/40 sand. AIR 21, ATP 1050, ISIP 0.

Set wireline retrievable bridge plug at 4250'.

Perforated the Pictured Cliffs at: 4038', 4044', 4050', 4056', 4064', 4070', 4079', 4086', 4093', 4100', 4106', 4112', 4117', 4123'. Total of 14 holes. Brokedown with 1100 gallons of 15% HCl. Frac'd with 97,000 gallons of water and 92,000# of 20/40 sand. AIR 1250, ATP 23, ISIP 0.



18. I hereby certify that the foregoing is true and correct

SIGNED

[Signature]

TITLE District Production Manager

DATE 9-17-79

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

slate