

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other ☐

2. NAME OF OPERATOR
El Paso Natural Gas Company

3. ADDRESS OF OPERATOR
P.O. Box 289, Farmington, NM 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
1100'S, 1820'E
AT SURFACE:
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☒
☒
☐
☐
☐
☐
☐
☐
☐

5. LEASE
SF 080673

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
San Juan 27-4 Unit

8. FARM OR LEASE NAME
San Juan 27-4 Unit

9. WELL NO.
125A

10. FIELD OR WILDCAT NAME
Tapacito PC Ext. & Blanco MV

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 8, T-27-N, R-4-W
NMPM

12. COUNTY OR PARISH
Rio Arriba

13. STATE
New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
6856' GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

10-12-80: TD 4120'. Ran 96 joints 7", 20 & 23#, K-55 intermediate casing 4109' set at 4120'. Cemented w/304 cu. ft. cement. WOC 12 hrs; held 1200#/30 minutes. (Temperature Survey was not taken)

10-16-80: TD 6354'. Ran 63 joints 4 1/2", 10.5K-55 casing liner 2395- set 3959-6354'. Float collar set at 6338'. Cemented w/417 cu. ft. cement. WOC 18 hours.

10-29-80; PBTD 6338'. Tested casing to 3500#, OK. Perfed Massive & Lower P.L. 5924, 5930, 5936, 5942, 5953, 5959, 5976, 5992, 6006, 6031, 6046, 6052, 6098, 6165, 6195, 6206, 6259, 6288' (one misfire at 5915') W/1 SPZ. Fraced w/ 52,000# 20/40 sand, 151,000 gal. wtr. Flushed w/ 8050 gal. wtr.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct


SIGNED D. G. Busco TITLE Drilling Clerk DATE November 25, 1980

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

NMOCC

*See Instructions on Reverse Side



BW

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

GPO : 1976 O - 214-149

10-30-80: Perfed 2 squeeze holes at 3720' set packer set 3530'. Cemented w/ 118 cu. ft. cement.
Perfed C.H. & Menefee:
5440, 5499, 5516, 5547, 5584, 5667, 5693, 5710, 5720
5743, 5753, 5759, 5837, 5844, 5850, 5870' w/1 SPZ
Fraced w/ 59,000# 20/40 sand, 162,000 gal
wtr. Flushed w/7800 gal. wtr.
11-31-80: Perfed P.C. 3739-62, 3769-89, 3801-24' w/2
Squeeze holes at 3770' Fraced w/ 68,000# 10/
20 sand, 78,000 gal. wtr. Flushed w/ 6400
gal. wtr.