

PROJECT PROPOSAL - New Drill / Sidetrack



Total Depth	7666	-1090	12	3000		6 1/4" Hole - 4 1/2", 10.5 ppt, J-55, STC casing. Circulate cement a minimum of 100' inside the previous casing string. 50% Excess. No open hole logs. Cased hole TDT with GR to surface.
-------------	------	-------	----	------	--	---

Logging Program

Intermediate Logs :	<input type="checkbox"/> Log only if show	<input type="checkbox"/> GR / ILD	<input type="checkbox"/> Triple Combo			
TD Logs :	<input type="checkbox"/> Triple Combo	<input type="checkbox"/> Dipmeter	<input type="checkbox"/> RFT	<input type="checkbox"/> Sonic	<input type="checkbox"/> VSP	<input checked="" type="checkbox"/> TDT

Additional Information :	Logging company to provide a sketch with all lengths, OD's & ID's of all tools prior to running in the hole. Cased hole TDT with GR to surface.
--------------------------	--

Comments :