

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPPLICATE*
(Other instructions on reverse side)

Form 9-331
Budget Bracket
LEASE DESIGNATION
MM 05792

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. WELL TYPE OIL ☐ GAS ☒ WELL ☐ OTHER ☐	6. IF INDENT, ATTACHED
2. NAME OF OPERATOR Sinclair Oil & Gas Company	7. UNIT AGREEMENT
3. ADDRESS OF OPERATOR 501 Lincoln Tower Bldg., 1860 Lincoln St., Denver, Colorado	8. FARM OR LEASE NAME Graham #5-111 Federal
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1000' f/South line and 1790' f/West line Section 1-27N-8W	9. WELL NO. 5
14. PERMIT NO. Mr. J.L.Ward, 3/22/66	10. FIELD AND POOL OR SURVEY OR AREA So. Blaine Pictured Cliff
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6735' G.L.	11. SEC., T., R., M., OR B. Sec. 1-27N-8W
	12. COUNTY OR PARISH San Juan
	13. STATE New Mexico

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data


NOTICE OF INTENTION TO		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF	WELL OR ALTER CASING	WATER SHUT-OFF	REPAIRING WELL
FRACURE TREAT	WELL RE-ENTER COMPLETE	FRACURE TREATMENT	ALTERING CASING
SHOOT OR ACIDIZE	ABANDON	SHOOTING OR ACIDIZING	ABANDON WELL
REPAIR WELL	CHANGE PLANS	(Other)	
(Other)		(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

17. DESCRIBE THE SCOPE OF COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) *

Well drilled to T.D. 7450', Ran 1-ES & GP-Density logs. Logs indicated well to be non-productive in both the Mesaverde and Dakota formations, but commercial gas production could be obtained from the Pictured Cliffs. In lieu of dualy completing in Dakota and Mesaverde, we now propose:

Set 33 sack cement plug 7250'-7350', 33 sack cement plug 5150'-5250', 33 sack cement plug 1550'-1650', 38 sack cement w/2% CaCl plug 3500'-3600', test top plug, set 1-1/2" casing at approx 3150', cement with 264 cu. ft, perforate Pictured Cliffs, treat if necessary, and complete.

Confirming verbal approval of 4/13/66 between Mr. R. B. Stahl of U.S.G.S. and Mr. J. E. Taylor of Sinclair.



18. I hereby certify that the foregoing is true and correct

SIGNED _____ TITLE **Chief Office Clerk** DATE **4/14/66**

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY: