

THIS IS AN INTENT TO ABANDON /
AS WELL AS AN ACIDIZE

9-331
1973

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form Approved.
Budget Bureau No. 42-R1424

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
✓ Sanan, Ltd.
3. ADDRESS OF OPERATOR
P.O. Box 255, Farmington, NM 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
✓ AT SURFACE: 1450' fs1 1190' fe1
AT TOP PROD. INTERVAL: same
AT TOTAL DEPTH: same
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☒
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☒
(other) ☐

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐
☐
☐

5. LEASE
✓ SF-030008
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
N/A
7. UNIT AGREEMENT NAME
N/A
8. FARM OR LEASE NAME
✓ Crab
9. WELL NO.
✓ 1
10. FIELD OR WILDCAT NAME
WAN Fruitland - P.C.
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
✓ S8-T26N-R12W, N.M.P.M.
12. COUNTY OR PARISH 13. STATE
San Juan New Mex.
14. API NO.
30-045-23246
15. ELEVATIONS (SHOW DF, KDB, AND WD)
5996 GR

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Propose moving on pulling unit, installing mastervalue, pressure testing 2 7/8" casing, swabbing hole to 1000', rig stripper head and perforate casing with 1 SPF from 1180-1188'. Acidize perfs with 250 gal. mud acid. If productive will run 1 1/2" tbg. with packer above perfs and complete natural. If non-productive, will plug & abandon by filling existing 2 7/8" to surface with Class B cement, & erect dry-hole marker & clean level & seed location in accordance with Federal regulations. Work to commence approximately August 15, 1979.

Subsurface Safety Valve: Manu. and Type _____

18. I hereby certify that the foregoing is true and correct

SIGNED W. R. Speer TITLE Agent DATE August 9, 1979


(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____

AUG 09 1979
U.S. GEOLOGICAL SURVEY
Set @



NMOCC