

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other - dry hole

2. NAME OF OPERATOR
Energy Reserves Group, Inc.

3. ADDRESS OF OPERATOR
P.O. Box 3280 - Casper, WY 82602

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 2,130' FNL & 660' FEL (SE/NE)
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

5. LEASE
14-20-603-2085

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Old Trading Post

9. WELL NO.
5

10. FIELD OR WILDCAT NAME
Bisti

11. SEC., T., R., OR BLK. AND SURVEY OR AREA
Sec 9-T 6N-R14W

12. COUNTY OR PARISH
San Juan

13. STATE
New Mexico

14. API NO.

15. ELEVATIONS TO TOP OF K.B. AND WD)
G.L. 6,040' K.B. 6' 0"

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL


PULL OR ALTER CASING

MULTIPLE COMPLETE CHANGE ZONES

ABANDON*

(other)

SUBSEQUENT REPORT OF:



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details including estimated date of starting any proposed work. If well is directionally drilled, measured and true vertical depths for all markers and zones pertinent to this work.)*

The above reference well was spudded @ 11:59 p.m., 12-1/4" hole to 521' (K.B.).

Ran 13 jts - 8-5/8" O.D. 24#, K-55, 8rth, R-3, S. Cemented w/350 sx Class "B" cement @ 12:45 a.m. 10-12-79. Good cement returns.

Nipple up and pressure tested BOPE to 800 psi - h

Drilled 7-7/8" hole to 5,000' and ran logs.

Permission is requested to plug and abandon per t between Mr. Jack Cook and Mr. Earl Beacher on 10- Subsurface Safety Valve: Menu. and Type

18. I hereby certify that the foregoing is true and correct


SIGNED Robert C. Miller TITLE Drig. Supt. DATE 10/20/79

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

ok Smith



NOV 06 1979

ACTING DISTRICT ENGINEER

Page 2

as follows:

Plug No. 1 - 4,790' - 4,620' w/50 sx of cement.
Plug No. 2 - 2,690' - 2,350' w/100 sx of cement.
Plug No. 3 - 1,100' - 850' w/100 sx of cement.
Plug No. 4 - 590' - 450' w/50 sx of cement.

Set marker in top of surface casing w/10-sx of cement.