

submitted in lieu of Form 3160-5

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Sundry Notices and Reports of Wells 20 SEP 21 PM 1:37

070 FARMINGTON, NM

1. Type of Well
GAS

5. Lease Number
SF-080505A

6. If Indian, All. or
Tribe Name

7. Unit Agreement Name

2. Name of Operator

**BURLINGTON
RESOURCES**

OIL & GAS COMPANY

3. Address & Phone No. of Operator

PO Box 4289, Farmington, NM 87499 (505) 326-9700

4. Location of Well, Footage, Sec., T, R, M

1150' FSL, 850' FEL, Sec. 8, T-28-N, R-6-W, NMPM

San Juan 28-6 Unit

8. Well Name & Number

San Juan 28-6 U #218

9. API Well No.

30-039-21394

10. Field and Pool

So. Blanco Pict. Cliffs

11. County and State

Rio Arriba Co, NM

12. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OTHER DATA

Type of Submission

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment

Type of Action

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☒ Casing Repair

☐ Altering Casing

☐ Other -

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut off

☐ Conversion to Injection

13. Describe Proposed or Completed Operations

It is intended to repair the casing in the subject well according to the attached procedure and wellbore diagram.



14. I hereby certify that the foregoing is true and correct.

Signed [Signature] (SDPC) Title Regulatory Supervisor Date 9/20/00
no

(This space for Federal or State Office use)

APPROVED BY _____ Title _____ Date 9/15/00

CONDITION OF APPROVAL, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

NMCCD

San Juan 28-6 Unit #218
Pictured Cliffs Slimhole Restimulation Procedure
P 08 28N 6W
Rio Arriba County, N.M.
Latitude: 36 Deg, 40.3 Min
Longitude: 107 Deg, 29.0 Min
API # 3003921394

Summary:

The subject well is a 1977 Pictured Cliffs slimhole completion through 2 7/8" casing. The casing did not test when the initial attempt to restimulate this well was done. The casing leak will now be isolated and a free point will be run to determine if casing is free below the leak. If so, the casing will be backed off as deep as possible. New casing will be run and tied back in and a bond log will be run. If the BLM requires a squeeze job the procedure will be written at that time. The new casing will then be pressure tested to 3700 psi and the cased hole interval will be cleaned-out to PBTD at 3,878' using air-mist and 1-1/4" drillstring. The Pictured Cliffs will be restimulated with 57,020 gal of 70Q N2 foamed 30# linear guar gel and 175,000# 20/40 mesh sand. The well will then be cleaned-up and returned to production.

- Comply with all NMOCD, BLM, and BR regulations. Conduct daily safety meetings for all personnel on location. Notify BR regulatory (Peggy Cole 326-9727) and the appropriate Regulatory Agency prior to pumping **any** cement job. If an unplanned cement job is required, **approval is required before the job can be pumped. If verbal approval is obtained, document the approval in Dims.** Allow adequate notice prior to the pump time for the Agency to witness the cementing operation.
- Inspect location and wellhead and install rig anchors prior to rig move.
- Construct blow pit.
- Contact area foreman 24-hrs. prior to beginning operations.

CASING REPAIR

1. MOL, hold safety meeting, & RU completion rig. Insure all safety equipment is strategically located and functioning properly. NU relief lines to blow pit. ND wellhead & NU 7-1/16" 3M BOP, stripping head, and blooie line. Test BOP.
2. PU and TIH with a 2-7/8" RBP and 1-1/4" tubing. Set RBP at 3,627' (top perf – 50'). Release from RBP. Spot 10' of sand on RBP. TOOH.
3. PU 1 jt. 2-7/8" tubing and screw into casing. MIRU wireline specialties. Freepoint 2-7/8" casing.
4. PU 2-7/8" packer. TIH with 2-7/8" packer on 1-1/4" tubing. Set packer at lowest 100% freepoint in casing. Pressure test casing below and above packer. Release packer and TOOH. If casing leak is below packer RDMO. If leak is above packer continue with step 5.
5. RIH with stringshot. Back off casing at lowest joint 100% free. RDMO wireline specialties.
6. Circulate hole clean. TOOH and lay down old 2-7/8" casing.
7. PU and TIH with new 2-7/8" casing. Screw in to existing casing.
8. Pressure test casing to 3700 psi for 15 minutes.
9. TIH with 1-1/4" tubing. Clean out to top of RBP. Latch on to 2-7/8" RBP and TOOH. Lay down RBP. PU 2-1/4" bit, TIH, & CO to PBTD. TOOH and lay down 1-1/4" tubing.
10. RDMO.

RIGLESS STIMULATION PROCEDURE

11. Install 2 7/8 In. 6.5 # N-80 EUE 8rd sub and 5,000 psi frac valve. Lay flowback line to pit.

12. Set two (2) 400 bbl frac tank(s) on location and fill with 720 bbl 2% KCl water. Treat tank with biocide prior to filling. Heat gel tank to 60-70 °F in winter.
13. RU stimulation company. Pressure test surface lines to 4,700 psi for 15 minutes. RU wireline company. Perforate an additional 8 holes at 3677', 3688', 3692', 3695', 3710', 3714', 3725', 3740' (see attached log copy) with 2-1/8" stripgun (14 gm 401 MT) charges. Perforate under packoff in one run with collar locator above gun. RD wireline company.
14. RU stimulation company to frac down 2 7/8" casing. Hold pre-job safety meeting with all personnel on location. Stimulate in 1 to 4 ppg stages at 35 BPM constant downhole rate with 57,020 gal of 70Q N2 foamed 30# linear guar gel and 175,000# 20/40 mesh Arizona sand. Maintain a bottom hole frac gradient of 0.55 psi/ft throughout job. When sand is in the hopper and the concentration begins to drop, call flush. Maintain previous stage's slurry and N2 rates. Flush to 100' above top perforation with +/- 395 fluid gals. **Maximum treating pressure is 3,700 psi.** Monitor bottomhole treating pressure, surface treating pressure, downhole rate, foam quality, and sand concentration with computer van. Treat in accordance to the enclosed schedule. Frac fluid will contain the following additives per 1000 gallons:
 - 30# WG-19 (Gelling agent pre-mixed in full tank)
 - 2.0 gal SSO-21M (Non-ionic surfactant pre-mixed in full tank)
 - 0.5# GBW-3 (Enzyme breaker mixed on fly)
 - 3.0 gal AQF-2 (Foamer mixed on fly)
 - 0.18# BE-6 (Bactericide pre-mixed in full tank)
 - 0.25 gal BA-20 (pH buffer mixed on fly)
15. Shut well in after frac and record ISIP. Record volume and empty remaining fluid in frac tanks to pit and RD stimulation company. Install flowback line above frac valve. Wait for 30 minutes to 1 hour before commencing flowback. Open well to pit in accordance to **flowback schedule enclosed in procedure**. If choke plugs off, shut well in and remove obstruction from choke and return to flowback schedule. **Do not replace with next larger choke size until schedule dictates.** Continue cleaning well up until fluid returns are negligible. **Take pitot gauges when possible.**
16. ND flowback line and frac valve. NU production valve with flow tee. NU flowback line.

SWAB RIG CLEAN-UP

17. MIRU Silver Star. PU and RIH with 2 1/4" sand bailer. CO to PBTD at 3878'. Monitor gas and water returns. **Take pitot gauges when possible.**
18. Continue cleaning up after frac until sand returns are a trace and fluid recovery is less than 2 BPH. TOOH. **Take final pitot gauge.**
19. RD and release swabbing unit.

Approve: David Cook 9/5/00
Team Leader

Approve: Bruce D. Boyer 9-12-00
Drilling Superintendent

VENDORS:

Stimulation:	Halliburton	325-3575
Swabbing:	Silverstar	327-7259

Frac Valve, & Flowback Line:	Dean Lingo	330-0144
---------------------------------	------------	----------

Scott Dobson 	Office - 326-9813	Home - 564-3244	Pager - 326-8036
---	-------------------	-----------------	------------------

6/26/00 - Casing leak
was found between 431'
& 1000'

SJ 28-6 Unit 218
Section 8P, T-28-N, R-6-W
Rio Arriba County, New Mexico
Pictured Cliffs
Wellbore Schematic
Lat 36° 40.3' Long 107° 29.0'

GL: 6821'
KB: 6831'

