

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐

2. NAME OF OPERATOR
El Paso Natural Gas Company

3. ADDRESS OF OPERATOR
P.O. Box 289, Farmington, NM 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1840'S, 1760'E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

5. LEASE
~~NM 03195-A~~ SF 078424

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
San Juan 29-7 Unit

8. FARM OR LEASE NAME
San Juan 29-7 Unit

9. WELL NO.
65A (PM)

10. FIELD OR WILDCAT NAME
Blanco MV & Basin Dakota

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 22, T-29-N, R-7-W
NMPM

12. COUNTY OR PARISH
Rio Arriba

13. STATE
New Mexico

14. API NO.


15. ELEVATIONS (SHOW DF, KDB, AND WD)
6772' GL

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other)

SUBSEQUENT REPORT OF:

☐
☒
☐
☐
☐
☐
☐
☐
☐



(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

7-21-80: PBDT 8036'. Tested casing to 4500#, OK. Perfed Cliff House & Menefee: 5236, 5254, 5280, 5309, 5329, 5337, 5344, 5365, 5371, 5377, 5403, 5410, 5417, 5477' W/1 SPZ. Fraced w/ 51,000# 20/40 sd, 102,000 gal.wtr. Flushed w/ 14,400 gal. wtr.

7-20-80: Perfed Massive & Lower Point Lookout: 5748, 5756, 5764, 5772, 5780, 5788, 5796, 5809, 5825, 5831, 5843, 5857, 5864, 5880, 5898, 5903, 5918, 5955, 5973, 6016, 6026, 6033, 6060, 6084, 6104, 6113' W/1 SPZ. Fraced w/ 86,000# 20/40 sd, 172,000 gal. wtr. Flushed w/ 15,300 gal. wtr.

7-19-80: Perfed Dakota 7822, 7825, 7832, 7834, 7836, 7838, 7840, 7842, 7851, 7853, 7908, 7910, 7936, 7940, 7986, 7988, 8005, 8008' W/1 SPZ. Fraced w/ 117,000# 20/40 sand, 108,000 gal. wtr. Flushed w/ 13,700 gal. wtr. Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED John D. Bradfield TITLE Drilling Clerk DATE July 30, 1980
ACCEPTED FOR RECORD

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

BY BW FARMINGTON DISTRICT

*See Instructions on Reverse Side

NMOCC