

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas ☒ well ☐ other

2. NAME OF OPERATOR
El Paso Natural Gas Company

3. ADDRESS OF OPERATOR
P.O. Box 289, Farmington, NM 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1030'S, 1540'E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☐
☒
☐
☐
☐
☐
☐
☐
☐

RECEIVED

AUG 29 1980

U. S. GEOLOGICAL SURVEY
FARMINGTON, N. M.

5. LEASE
SF-079514

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
San Juan 29-7 Unit

8. FARM OR LEASE NAME
San Juan 29-7 Unit

9. WELL NO.
77A

10. FIELD OR WILDCAT NAME
Basin Dakota & Blanco Mesa Verde


11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 33, T-29-N, R-7-W
NMPM

12. COUNTY OR PARISH
Rio Arriba

13. STATE
New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB AND WD)
6227' GL



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

-21-80: Perfed Dakota:
7226,7231,7236,7241,7246,7252,7258,7264,7274,7385' W/1 SPZ. Fraced w/150,000#
20/40 sand, 75,000 gal. wtr. Flushed w/14,800 gal. wtr.

Perfed 7317,72324,7331,7346,7352,7357,7371,7376,7382,7396,7406,7414,7420,7426'
W/1 SPZ. Fraced w/230,000# 20/40 sand, 115,000 gal. wtr. Flushed w/15,246 gal.
wtr.

-22-80: Perfed Massive & Lower Point Lookout:
5136,5140,5144,5151,5155,5159,5170,5174,5189,5200,5204,5254,5272,5320,5326,
5350,5388,5408,5424,5468,5478,5520,5540,5558' W/1 SPZ. Fraced w/61,500#
20/40 sand, 123,000 gal. wtr. Flushed w/13,356 gal. wtr.

Perfed Cliff House & Menefee: (Continued on Reverse side)
Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Drilling Clerk DATE August 28, 1980

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL IF ANY

SEP 02 1980

*See Instructions on Reverse Side

FARMINGTON DISTRICT
BY [Signature]

NMOCC

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

GPO : 1976 O - 214-149

Perfed Cliff House & Menefee:
4588,4594,4600,4606,4632,4640,4688,4695,4702,4721,4770,
4778,4728,4834,4840,4885,4954,4968,5002, W/1 SPZ. Fraced
W/ 71,000 # 20/40 sand, 142,000 gal. wtr. Flushed W/ 12,478
gal. wtr.