PROCEDURE - PAGE 2

LEASE	NAME:	Hughes LS	WELL	NUMBER:	2 A

- 6. Frac PC dn csg w/70 quality foamed 2% KCl water and 20/40 sd @ 2500 psi max. Use attached design graph to calculate volumes. Call Denver to confirm design. SI for 2 hrs and flow back to pit thru 1/2" tapped bull plug.
- 7. Kill well w/2% KCl water. RIH w/2-3/8" tbg w/muleshoe on btm and F/N w/exp check valve 1 jt off btm. Position seal assembly and blast joints to land the tbg $@ \pm 5650'$ with blast jts across from PC intervals. CO to Model D pkr w/foam. Knock out plug and land 2-3/8" long string.
- 8. RIH w/1-1/4" tbg W/SN, pump out plug and perforated, orange peeled sub on btm. Land short string @ \pm btm of PC perfs.
- 9. NDBOP, NUWH. Pump out check valve from long string. Swab in Mesa Verde if necessary. Pump out plug in short string and kick around w/N_2 . FTCU.
- 10. SI PC for AOF.