

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other

2. NAME OF OPERATOR

EL PASO NATURAL GAS CO.

3. ADDRESS OF OPERATOR

BOX 990, FARMINGTON, NEW MEXICO

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE: 1550'N, 800'W

AT TOP PROD. INTERVAL:

AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☒
☒
☐
☐
☐
☐
☐
☐
☐

5. LEASE

SF 078487C

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

SUNRAY

9. WELL NO.

1A

10. FIELD OR WILDCAT NAME

BLANCO MESA VERDE

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Sec. 5, T-29-N, R-8-W

NMPM

12. COUNTY OR PARISH

SAN JUAN

13. STATE

NEW MEXICO

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)

6225' GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

3/31/78: T.D. 3230'. Ran 80 jts. 7", 20#, K-55 intermediate casing, 3216' set at 3230'. Cemented with 296 cu. ft. cement. WOC 12 hours, held 1200#/30 minutes. Top of cement at 2100'.

4/3/78: T.D. 5541'. Ran 80 jts. 4 1/2", 10.5#, K-55 casing liner, 2488' set 3053-5541'. Float collar set at 5523'. Cemented with 431 cu. ft. cement. WOC 18 hours.

5/7/78: PBTD 5523'. Tested casing to 3500#, OK. Perfed Upper and Lower P.B. 5118, 5123, 5128, 5133, 5138, 5143, 5148, 5153, 5158, 5168, 5180, 5196, 5204, 5224, 5242, 5256, 5274, 5328, 5346, 5379, 5397, 5426, 5466, 5481' w/1 SPZ.

Subsurface Safety Valve: Manu. and Type _____

Set @ _____

18. I hereby certify that the foregoing is true and correct

SIGNED M. G. Buers TITLE Drilling Clerk DATE 5/11/78

(This space for Federal or State office use)


APPROVED BY _____

TITLE _____

DATE _____

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side



Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

GPO : 1976 O - 214-149

Fraced with 78,000# 20/40 sand and 161,000 gallons
water. Flushed with 6500 gallons water. Perfed
C.H. and Men. 4436,4551,4558,4565,4583,4593,4632,
4643,4669,4682,4691,4714,4781,4802,4840,4897,
4914,4921,4928,4945,4995,5003,5011' w/1 SPZ. Fraced
with 86,000# 20/40 sand and 162,000 gallons water.
Flushed with 6500 gal. water.