


Form 100-1



(SUBJECT IN TRIPLICATE)
**UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY**

Form 100-1, G.S.M.A.
Location Santa Fe
Lump No. 000245
Date ME/4 Dec. 20

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	STATEMENT REPORT OF WATER SHUT-OFF
NOTICE OF INTENTION TO CHANGE PLANT	STATEMENT REPORT OF SHUTTING ON ADDRESS
NOTICE OF INTENTION TO TEST OTHER SHUT-OFF	STATEMENT REPORT OF ALARMING CHARGE
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL	STATEMENT REPORT OF RE-DRILLING OR REPAIR
NOTICE OF INTENTION TO CHANGE PLANT <u>FRAC</u>	STATEMENT REPORT OF ADJUSTMENT
NOTICE OF INTENTION TO PUMP OR ALTER CHARGE	SUPPLEMENTARY WELL HISTORY
NOTICE OF INTENTION TO ABANDON WELL	

(CONTINUE ABOVE ON OTHER BACKS OF REPORT, NOTICE, OR OTHER DATA)

APR 11 20 1962


Owner _____
Well No. 1 is located 639 ft. from (N) line and 945 ft. from (E) line of sec. 20

ME/4 Dec. 20 1-22-4 1-2-4 ME/4
Blanco, Nevada San Juan New Mexico

The elevation of the derrick floor above sea level is 3504 ft. O. L.

DETAILS OF WORK

(State nature of work and extent thereof as to depth, casing, tubing, and length of proposed casing, tubing, and other important proposed work)



Move in rig set plug below 7th seg. shoe, side track, and drill w/gas from present T.D. of 4400 to approximate T.D. of 6400' set 4-1/2" casing from surface to T.D. w/approximately 200 segs. cement. Perforate and free in Dakota and Mesaverde sections. Run packer for pump separation. Run 2-3/8" SUE 4.700 tubing and complete well with Dakota protecting thru tubing and Mesaverde thru tubing-casing annulus.

ILLEGIBLE

I understand that this plan of work must receive approval by the Geological Survey before operations may be commenced.

Company Balbi-Taylor Oil Corporation
Address P.O. Box 1100
Farmington, New Mexico
Original signed by
By G. T. HIGGINBOTHAM
G. T. Higginbotham
Title District Superintendent