


COPY TO U. S. G.

(SUBMIT IN TRIPLICATE)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYLand Office Santa Fe  
Lease No. 076137  
Unit W. D. Heath "A"  
East 1/2, Section 17  
Designated Drilling Unit

## SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	<input checked="" type="checkbox"/>	SUBSEQUENT REPORT OF WATER SHUT-OFF	
NOTICE OF INTENTION TO CHANGE PLANS		SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF		SUBSEQUENT REPORT OF ALTERING CASING	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL		SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE		SUBSEQUENT REPORT OF ABANDONMENT	
NOTICE OF INTENTION TO PULL OR ALTER CASING		SUPPLEMENTARY WELL HISTORY	
NOTICE OF INTENTION TO ABANDON WELL			

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

Farmington, New Mexico August 21, 1953Well No. 2 is located 1020 ft. from N line and 960 ft. from E line of sec. 17NE 1/4 of Section 17  
(1/4 Sec. and Sec. No.)T-29-N  
(Twp.)R-9-W  
(Range)RMPL  
(Meridian)Blanco-Mesa Verde  
(Field)San Juan  
(County or Subdivision)New Mexico  
(State or Territory)The elevation of the derrick floor above sea level is 5730 ft. (ungraded ground)

## DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

We propose to drill the above well to approximately 4800 feet. Rotary tools will be used to total depth. Casing will be set on top of Cliffhouse. Mesa Verde formation will be drilled with gas and cleaned out with gas after shot with SMC.

The following casing program is proposed:

Size	Depth	Cement	Remarks
9-5/8"	250'	200	175% of calculated amount to circulate.
7"	3800'	300	150% of calculated amount to fill 1260' above shoe.

Copies of location plat are attached. A copy of any survey taken will be submitted upon completion of well.

I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Stanolind Oil and Gas CompanyAddress Box 467Farmington, New Mexico

By

L. O. Spivey

Title

Field Superintendent

# DEFENSE COMMISSION


Label 5-1-54  
STANLIND OIL GAS W.D. HEATH AP 2  
(General) (1) (Weight)

Name ROBERT M. MESSERSMITH BLANCH

No. 3-3-5 dedicated to the War

SECTION 17 SHIP BY W

		USA W.D. HEATH (Sgt. F. 67337) R. D. ALLEN
		STANLIND



**ILLEGIBLE**

M.W. HINCH  
 Field Engineer  
 STANLIND OIL GAS  
 Box 507, Fairbairn, N.D.

OIL CONSERVATION COMMISSION		
AZTEC DISTRICT OFFICE		
No. Copies Received <u>3</u>		
DISTRIBUTION		
	NO. FURNISHED	
Operator		
Santa Fe	1	
Proration Office		
State Land Office		
U. S. G. S.	1	
Transporter		
File	1	✓