Approved by

Conditions of approval, if any:

representations as to any matter within its jurisdiction.

## **UNITED STATES** DEPARTMENT OF THE INTERIOR BUREALL OF LAND MANAGEMENT

FORM APPROVED Budget Bureau No. 1004-0135 expires: March 31, 1993

BUNEAU OF LAN	REGERA			
SUNDRY NOTICES AN	D REPORTS ON WELLS	5. Lease Designation and Serial N	lo.	
De and the form for proposals to drill or		SF 07 <b>§</b> 337		
Use "APPLICATION FOR F	PERMIT - " for such proposals 50 SEP - 7 Proposals	12: 35 If Indian, Allottee or Tribe Nam	18	
. Holling of the control of the cont			: .	
0/0 175 ON,		ON, NIT Unit or CA, Agreement Des	1 1 If Unit or CA, Agreement Designation	
i. Type of Well Oil Well Well Other		8. Well Name and No.		
Well Well Uniter	Attention:	Heath Gas Com "E"	1	
Amoco Production	Lois Raeburn/Gail Jefferson	Gail Jefferson 9. API Well No.		
3. Address and Telephone No.	3004508463 (303) 830-6157			
P.O. Box 800, Denver, Colorado 80201			10. Field and Pool, or Exploratory Area  Blanco Mesaverde	
4. Location of Well. (Footage, Sec., T., R., M., or Survey Description	on)	11. County or Parish, State	averde	
990FSL 1650FWL 5	Sec. 8 T 29N R 9W N	11. County of 1 ansit, State		
		San Juan	New Mexico	
2. CHECK APPROPRIATE BOX(s)	TO INDICATE NATURE OF NOTICE, R	EPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACT			
Notice of Intent	Abandonment Recompletion	Change of Plans  New Construction		
Notice of Intent	Plugging Back	Non-Routine Fracturing		
Subsequent Report	Casing Repair	Water Shut-Off		
Final Abandonment Notice	Altering Casing Other Bradenhead	Conversion to Injection Dispose Water		
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	(No	ote: Report results of multiple completion or completion Report and Log form. )	Well Completion or	
13. Describe Proposed or Completed Operations (Clearly state all p			directionally drilled giv	
subsurface locations and measured and true vertical de	pths for all markers and zones pertinent to this work.)*		. a, a, g	
Amoco Petroleum Company would like to	preform Bradenhead repairs on the subject	well.		
See attached procedures.				
See attached procedures.				
		DEAGNE	The name of the contract of th	
		可限の問題を		
		M orn 4 0 1005	1 	
		n = 256 1 2 1000		
		ONL COME DA	¥Ç	
			57B	
		dist. 3		
			.20.1 (1.5)	
14. I hereby certify that the torogoing is true and correct  Signed	hus not	A . *	08-06-1995	
Signed Signed Rale	Title Staff	Assistant Date		
(This space for Federal or State office use)		APPRO	YED	
		•.		

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictions or fraud representations as to any matter within its jurisdiction. \* See Instructions on Reverse

## HEATH GAS COM /E/ #1

**VERSION:** 

#1

Date:

August 3, 1995

Budget:

DRA/Repair Well

Repair Type:

**Bradenhead Remediation** 

## **OBJECTIVES:**

Remediate surging black water to insure zonal isolation behind casing 1.

2. Place well back on production

PERTINENT INFORMATION:

Location:

990' FSL x 1650' FWL, N08-T29N-R09W

County:

San Juan

Horizon: MV API #: 30-045-08463

State:

New Mexico

Engr: Kolodzie

Lease:

Well Flac:

924187

Phone: H--(303)987-0817

W--(303)830-4769

P--(303)

**CSG** 

**ECONOMIC EVALUATION:** 

APC WI:

100%

MV Prod. Before Repair:

0

**MCFD** 

**Estimated Cost:** 

\$38,800

MV Anticipated Prod.:

**MCFD** 

Payout:

? Months

Max Cost -12 Mo. P.O.

\$

PV15:

**\$M** 

Max Cost PV15:

\$M

Note: Economics will be run on all projects that have a payout exceeding ONE year.

FORMATION TOPS: (Estimated formation tops)

Nacimento:

Menefee:

Ojo Alamo: Point Lookout:

1950-2130'

Kirtland Shale:

Mancos Shale:

Fruitland:

Gallup:

Pictured Cliffs: Lewis Shale:

Dakota:

Cliff House:

3775'

Morrison:

Graneros:

BRADENHEAD TEST INFORMATION:

Test Date: 6/09/95 Tubing: 190 psi Casing: 300 psi BH: 80 psi

Time BH**CSG** INT 5 min 80 300 N/A 10 min 0 300 N/A 15 min 0 300 N/A

## **DETAILED PROCEDURE:**

- 1. Contact Federal or State agency prior to starting repair work.
- 2. Catch gas and/or water sample off of bradenhead and casing, and have analyzed.
- 3. Install and/or test anchors.
- 4. MIRUSU. Check and record tubing, casing and bradenhead pressures.
- 5. Blow well down, kill well if necessary with 2% KCL.
- 6. Nipple down well head, nipple up and pressure test BOP's.
- 7. Trip in the hole and tag PBTD, check for fill, trip and tally out of hole with tubing checking condition of tubing.
- 8. Trip in the hole with bit and scraper for the intermediate casing and trip in to the top of the liner. Trip out of the hole with bit and scraper. Trip in hole with second bit and scraper and run from the top of the liner to the top of the perforations. A seating nipple and standing valve may be run in order to pressure test the tubing.
- 9. Trip in the hole with RBP and PKR. Set RBP 50-100 ft. above perforations. Trip out of hole one joint and set PKR and pressure test RBP to 1500 psi. Release PKR, spot sand on RBP and pressure test csg to 1000 psi. If no leak is found, trip out of hole with PKR and skip to step 11.
- 10. Trip out of hole isolating leak in liner, if any. If a liner leak is found, establish injection rate and check for circulation around liner top. Also, determine if there is a leak above the top of the liner. Trip out of hole with PKR.
- 11. Determine from well file and history, the interval a CBL needs to be run between the RBP and the surface. If a CBL is needed, run CBL over the interval necessary under 1000 psi and report results to Denver. Different size CBL tools may be required in the liner versus the intermediate casing.
- 12. If there are no casing leaks, skip to step 14.
- 13. If there is a leak in the liner and a leak above the top of the liner, trip in hole with a RBP that fits the liner and a PKR that fits the intermediate casing. Set RBP 30-60' below the top of the liner. Release PKR and trip out of hole isolating leak in the intermediate casing.
- 14. Based on the location of the leak, if any, and the results of the CBL, perforate casing if necessary with 4 JSPF and circulate dye if possible to determine cement volume. Depending on the depth of the hole and circulating pressure, a PKR or a cement retainer may be needed.
- 15. Mix and pump sufficient cement (class B or equivalent with two hour setting time) to circulate to surface, if circulation to surface is possible. Shut bradenhead valve and attempt to obtain a squeeze pressure and WOC.

- 16. Trip out of hole. Trip in the hole with bit and scraper and drill out cement and pressure test casing. Re-squeeze leaks if casing fails pressure test.
- 17. If cement is not circulated to the surface, it may be necessary to run another CBL (and/or temperature survey 8-10 hours after cementing) and repeat steps 14 thru 16.
- 18. Trip in the hole with retrieving head for RBP, circulate sand off of RBP and trip out of hole with plug.
- 19. If there is a leak in the liner top, trip in hole with a PKR. If there is no leak in the liner top, skip to step 22.
- 20. Mix and pump sufficient cement (class B or equivalent with two hour setting time) to squeeze liner top. Attempt to obtain a squeeze pressure and WOC.
- 21. Trip in the hole with bit and scraper and drill out cement and pressure test casing. Re-squeeze leak if liner top fails pressure test.
- 22. If there is a second RBP in the liner, trip in the hole with a retrieving head, circulate sand off of the RBP and trip out of hole with the plug.
- 23. If there is a leak in the liner or squeeze work is required based on the CBL, perforate casing, if necessary with 4 JSPF. Trip in hole with a cement retainer and set above the leak or perforations.
- 24. Mix and pump sufficient cement (class B or equivalent with two hour setting time) and attempt to obtain a squeeze pressure and WOC.
- 25. Trip in the hole with bit and scraper and drill out cement and pressure test casing. Re-squeeze leaks if casing fails pressure test.
- 26. Trip in the hole with retrieving head for RBP set in the liner, circulate sand off of RBP with 2% KCL and trip out of hole with plug.
- 27. Trip in hole with a sawtooth collar and/or bailer and clean out to PBTD and trip out of hole.
- 28. Trip in the hole with the production string (1/2 mule shoe on bottom and a seating nipple one joint off bottom), land tubing to original depth. Nipple down BOP's, nipple up well head.
- 29. Swab well in and put well on production.
- 30. Rig down move off service unit.
- 31. Take final bradenhead pressures and log date/pressures in CRWS.

If problems are encountered, please contact: Stan Kolodzie (W) (303) 830-4769 (H) (303) 987-0817