

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Sundry Notices and Reports on Wells

1. Type of Well
GAS

2. Name of Operator

**BURLINGTON
RESOURCES**

OIL & GAS COMPANY

3. Address & Phone No. of Operator

PO Box 4289, Farmington, NM 87499 (505) 326-9700

4. Location of Well, Footage, Sec., T, R, M

1805' FNL, 1975' FWL, Sec. 27, T-30-N, R-7-W, NMPM

5. Lease Number
NMSF-079074

6. If Indian, All. or
Tribe Name

7. Unit Agreement Name

San Juan 30-6 Unit

8. Well Name & Number

San Juan 30-6 U #38B

9. API Well No.

30-039-26780

10. Field and Pool

Blanco Mesaverde

11. County and State

Rio Arriba Co, NM

12. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OTHER DATA

Type of Submission

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment

Type of Action

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☒ Other -

☒ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut off

☐ Conversion to Injection

13. Describe Proposed or Completed Operations

It is intended to complete the subject well in the Mesaverde formation only instead of the Mesaverde and Dakota as permitted. Attached is a new C-102 plat, operations plan, BOP diagram and production facilities schematic.

RECEIVED
APR 15 PM 1:45
BUREAU OF LAND MANAGEMENT, NMA

ACCEPTED FOR FILE

FARMINGTON FIELD OFFICE
BY *[Signature]*

14. I hereby certify that the foregoing is true and correct.

Signed Nancy Olthman for Title Regulatory Supervisor Date 4/11/02
no

(This space for Federal or State Office use)

APPROVED BY /s/ Jim Lovato Title _____ Date APR 17
CONDITION OF APPROVAL, if any:

District I
PO Box 1980, Hobbs, NM 88241-1980

District II
PO Drawer DD, Artesia, NM 88211-0719

District III
1000 Rio Brazos Rd., Aztec, NM 87410

District IV
PO Box 2088, Santa Fe, NM 87504-2088

State of New Mexico
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION
PO Box 2088
Santa Fe, NM 87504-2088

Form C-102

Revised February 21, 1994

Instructions on back

Submit to Appropriate District Office

State Lease - 4 Copies

Fee Lease - 3 Copies

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-039-26780		Pool Code 72319	Pool Name Blanco Mesaverde
Property Code 7469	Property Name SAN JUAN 30-6 UNIT		Well Number 388
GRID No. 14538	Operator Name BURLINGTON RESOURCES OIL & GAS COMPANY		Elevation 6890'

10 Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
F	27	30N	7W		1805	NORTH	1975	WEST	RIO ARriba

11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
Dedicated Acres MV-W/320		Joint or Infill		Consolidation Code		Order No.			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>16</p> <p>5282.64'</p> <p>1805'</p> <p>1975'</p> <p>660'</p> <p>LAT: 36°47.2' N LONG: 107°33.6' W</p> <p>27</p> <p>NMSF-079074</p> <p>5280.00'</p> <p>5276.04'</p>	<p>17 OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.</p> <p><i>Nancy Oltmanns for</i></p> <p>Signature</p> <p>Peggy Cole</p> <p>Printed Name</p> <p>Regulatory Supervisor</p> <p>Title</p> <p>Date</p>
	<p>18 SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>MAY 8, 2001</p> <p>Date of Survey</p> <p>Signature and Seal of Professional Surveyor</p> <p><p>Certificate Number 6857</p></p>

OPERATIONS PLAN

Well Name: San Juan 30-6 Unit #38B
Location: 1805' FNL, 1975' FWL, Section 27, T-30-N, R-7-W
Rio Arriba County, New Mexico
Latitude 36° 47.2, Longitude 107° 33.6
Formation: Blanco Mesa Verde
Elevation: 6890' GL

<u>Formation Tops:</u>	<u>Top</u>	<u>Bottom</u>	<u>Contents</u>
Surface	San Jose	2762'	
Ojo Alamo	2762'	2952'	aquifer
Kirtland	2952'	3317'	
Fruitland	3317'	3792'	gas
Pictured Cliffs	3792'	3937'	gas
Lewis	3937'	4482'	gas
Intermediate TD	4187'		
Huerfanito Bentonite	4482'	4817'	gas
Chacra	4817'	5607'	gas
Massive Cliff House	5607'	5662'	gas
Menefee	5662'	5987'	gas
Point Lookout	5987'		gas
Total Depth	6387'		

Logging Program:

Mud Logs/Coring/DST -
Mud logs - none
Coring - none
DST - none
Open hole - none
Cased hole - Gamma Ray, Cement bond - surface to TD

Mud Program:

<u>Interval- MD</u>	<u>Type</u>	<u>Weight</u>	<u>Vis.</u>	<u>Fluid Loss</u>
0- 300'	Spud	8.4-9.0	40-50	no control
300- 4187'	LSND	8.4-9.0	30-60	no control
4187- 6387'	Air/Mist/N2*	n/a	n/a	n/a

Pit levels will be visually monitored to detect gain or loss of fluid control.

*Nitrogen might be used in conjunction with or instead of air to prevent a down hole fire.

Casing Program (as listed, the equivalent, or better):

<u>Hole Size</u>	<u>Measured Depth</u>	<u>Csg Size</u>	<u>Weight</u>	<u>Grade</u>
12 1/4"	0' - 300'	9 5/8"	32.3#	H-40
8 3/4"	0' - 4187'	7"	20.0#	J-55
6 1/4"	4087' - 6387'	4 1/2"	10.5#	J-55

Tubing Program: 0' - 6387' 2 3/8" 4.7# J-55

BOP Specifications, Wellhead and Tests:

Surface to Intermediate TD -

11" 2000 psi minimum double gate BOP stack (Reference Figure #1). After nipple-up prior to drilling out surface casing, rams and casing will be tested to 600 psi for 30 minutes.

Intermediate TD to Total Depth -

11" 2000 psi minimum double gate BOP stack (Reference Figure #1). After nipple-up prior to drilling out intermediate casing, rams and casing will be tested to 1500 psi for 30 minutes.

ACCEPTED FOR PLANNING

APR 17 2012

FARMINGTON FIELD OFFICE
BY *[Signature]*

Surface to Total Depth -

2" nominal, 2000 psi minimum choke manifold (Reference Figure #3).

Completion Operations -

7 1/16" 2000 psi double gate BOP stack (Reference Figure #2). After nipple-up prior to completion, pipe rams, casing and liner top will be tested to 2000 psi for 15 minutes.

Wellhead -

9 5/8" x 7" x 2 3/8" x 2000 psi tree assembly.

General -

- Pipe rams will be actuated once each day and blind rams will be actuated once each trip to test proper functioning.
- An upper kelly cock valve with handle available and drill string valves to fit each drill string will be available on the rig floors at all times.
- BOP pit level drill will be conducted weekly for each drill crew.
- All BOP tests & drills will be recorded in daily drilling reports.
- Blind and pipe rams will be equipped with extension hand wheels.

Cementing:

9 5/8" surface casing - cement with 201 sx Type III cement with 1/4# Celloflake/sx and 2% calcium chloride (282 cu.ft. of slurry, 200% excess to circulate to surface). WOC 8 hrs. Test casing to 600 psi for 30 minutes.

Saw tooth guide shoe on bottom. Bowspring centralizers will be run in accordance with Onshore Order #2.

7" intermediate casing - Lead w/385 sx Premium Lite cmt w/3% calcium chloride, and 0.25 pps Flocele, 5 pps LCM-1, 0.4% fluid loss, 0.4% SMS. Tail w/90 sx Type III cmt w/1% calcium chloride, 0.2% fluid loss and 0.25 pps Flocele (944 cu.ft. of slurry, 50% excess to circulate to surface.) WOC minimum of 8 hours before drilling out intermediate casing. If cement does not circulate to surface, a CBL or temperature survey will be run to determine TOC. Test casing to 1500 psi for 30 minutes.

See attached alternative intermediate lead slurry.

7" intermediate casing alternative two stage: Stage collar at 3217'. First stage: cement with 44 sx Premium Lite cmt w/3% calcium chloride, 0.25 pps Flocele, 5 pps LCM-1, 0.4% fluid loss, 0.4% SMS. Tailed w/90 sx Type III cmt w/1% calcium chloride, 0.25 pps Flocele, 0.2% fluid loss. Second stage: 341 sx Premium Lite cmt w/3% calcium chloride, 0.25 pps Flocele, 5 pps LCM-1, 0.4% fluid loss, 0.4% SMS (944 cu.ft., 50% excess to circulate to surface).

Cement nose guide shoe on bottom with float collar spaced on top of shoe joint. Bowspring centralizers spaced every other joint off bottom, to the base of the Ojo Alamo at 2952'. Two turbolating centralizers at the base of the Ojo Alamo at 2952'. Bowspring centralizers spaced every fourth joint from the base of the Ojo Alamo to the base of the surface casing.

4 1/2" Production Liner - Cement to circulate liner top. Pump 167 sx Premium Lite cmt w/0.25 pps Celloflake, 0.3% CD-32, 6.25 pps LCM-1, 1% fluid loss (330 cu.ft., 40% excess to circulate liner top). WOC a minimum of 18 hrs prior to completing.

Note: If open hole logs are run, cement volumes will be based on 25% excess over caliper volumes.

ACCEPTED FOR ALCOA
APR 17 1992
FARMINGTON OFFICE
BY

Cement nose guide shoe on bottom with float collar spaced on top of shoe joint. The liner hanger will have a rubber packoff.

- If hole conditions permit, an adequate water spacer will be pumped ahead of each cement job to prevent cement/ mud contamination or cement hydration.

Special Drilling Operations (Air/Mist Drilling):

The following equipment will be operational while air/mist drilling:

- An anchored blooie line will be utilized to discharge all cuttings and circulating medium to the blow pit a minimum of 100' from the wellhead.
- The blooie line will be equipped with an automatic igniter or pilot light.
- Compressors will be located a minimum of 100' from the wellhead in the opposite direction from the blooie line.
- Engines will have spark arresters or water cooled exhaust.
- The rotating head will be properly lubricated and maintained.
- A float valve will be utilized above the bit.
- Mud circulating equipment, water, and mud materials will be sufficient to maintain control of the well.


Additional Information:

- The Mesa Verde formation will be completed.
- No abnormal temperatures or hazards are anticipated.
- Anticipated pore pressures are as follows:

Fruitland Coal	300 psi
Pictured Cliffs	600 psi
Mesa Verde	700 psi
- Sufficient LCM will be added to the mud system to maintain well control, if lost circulation is encountered below the top of the Pictured Cliffs.
- The west half of Section 27 is dedicated to the Mesa Verde.
- This gas is dedicated.


Brennan D. Hurt
Drilling Engineer

4/15/2002
Date



BURLINGTON RESOURCES

Completion/Workover Rig BOP Configuration 2,000 psi System




Minimum BOP Installation for all Completion/Workover Operations. 7-1/16" bore, 2000 psi minimum working pressure double gate BOP to be equipped with blind and pipe rams. A stripping head to be installed on the top of the BOP. All BOP equipment is 2000 psi working pressure or greater excluding 500 psi stripping head.

Figure #2

BURLINGTON RESOURCES

Drilling Rig Choke Manifold Configuration 2000 psi System




Choke manifold installation from Surface Casing Point to Total Depth. 2,000psi working pressure equipment with two chokes.

Figure #3

Burlington Resources

Drilling Rig 2000 psi System




BOP Installation from Surface Casing Point to Total Depth. 11" Bore 10" Nominal, 2000 psi working pressure double gate BOP to be equipped with blind rams and pipe rams. All BOP equipment is 2,000 psi working pressure or greater excluding 500 psi stripping head.

Figure #1

ACCEPTED FOR RECORD

APR 17 2002

FARMINGTON FIELD OFFICE



PLAT #1

**ANTICIPATED
PRODUCTION FACILITIES
FOR A
MESA VERDE WELL**