

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE*
(Other instructions on reverse side)

14-20-603-5029

Form approved
Budget Bureau No. 42-R1424.

SUNDRY NOTICES AND REPORTS ON WELLS

(☒ not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. **Zoller and Danneberg**
WELL ☐ WELL ☐ OTHER ☐

2. NAME OF OPERATOR
219 Patterson Building - Denver, Colorado 80202

3. ADDRESS OF OPERATOR

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*
See also space 17 below.)
At surface

5224' Ground

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

Navajo

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

~~Navajo~~

UNIT AGREEMENT NAME
Pajarito-Navajo

8. FARM OR LEASE NAME
#1

9. WELL NO.
Wildcat

10. FIELD AND POOL, OR WILDCAT
20-29N-17W, 11NPN

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
San Juan New Mexico

12. COUNTY OR PARISH 13. STATE

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

(Other) ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

ABANDON* ☐

CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐

FRACTURE TREATMENT ☐

SHOOTING OR ACIDIZING ☐

(Other) ☐

REPAIRING WELL ☒

ALTERING CASING ☐

ABANDONMENT* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)


Operation plugged and abandoned well and well 14-20-603-5029 in following manner and in accordance with U.S.G.S. instructions:

Cement Plugs: 7100'-7200' w/37% sax in 9-5/8" casing.
6100'-6200' w/27% sax in 9-5/8" casing.
Shot off 2200' of 9-5/8" casing - recovered 71% joints. Hole from 2208' to 4716' cased w/9-5/8" casing w/500 sax cement.
4066' - 4700' w/10 sax in 9-5/8" casing across shoe and in 9-5/8" casing.
4280' - 4380' w/40 sax in 9-5/8" casing; across parted tool joint at 4331' which made water from DeChelly.
1650' - 1750' w/75 sax in 12-1/4" casing.
450' - 550' w/75 sax in 12-1/4" casing.
0' - 15' w/10 sax in 13-3/8" casing with marker imbedded.

Cleaned location. Ready for inspection.



Agent for Operator



18. I hereby certify that the foregoing is true and correct

SIGNED

John F. Mitchell

TITLE

DATE

(This space for Federal or State office use)

APPROVED BY

LM

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations; and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.