


Form 9-351a
(Feb. 1951)


(SUBMIT IN TRIPLICATE)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Land Office **SANTA FE**
Lease No. **SF 080380-A**
Unit _____

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL.....	SUBSEQUENT REPORT OF WATER SHUT-OFF.....	X
NOTICE OF INTENTION TO CHANGE PLANS.....	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING.....	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF.....	SUBSEQUENT REPORT OF ALTERING CASING.....	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL.....	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR.....	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE.....	SUBSEQUENT REPORT OF ABANDONMENT.....	
NOTICE OF INTENTION TO PULL OR ALTER CASING.....	SUPPLEMENTARY WELL HISTORY.....	
NOTICE OF INTENTION TO ABANDON WELL.....		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

NOVEMBER 16, 19 **60**

BLANCO 29-12

Well No. **1-7** is located **1199** ft. from **XX** line and **890** ft. from **E** line of sec. **7**


SE SE 7 (1/4 Sec. and Sec. No.)	30N (Twp.)	12W (Range)	MRP (Meridian)
UNDERSIGNATED (DAKOTA) (Field)	SAN JUAN (County or Subdivision)	NEW MEXICO (State or Territory)	

The elevation of the ~~surface~~ **ungr grad** above sea level is **5596** ft.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Drilled 8-3/4" hole to 5864' and reduced hole to 7-7/8" to total depth of 6333'. Ran 16 jts 4-1/2" OD 11.6# J-55, 8 RD and 184 jts 4-1/2" 9.5# J-55, 8 RD csg with Baker guide shoe and float collar, with Baker DV tool, T.R. 6330' set at 6331' with DV tool at 1800'. Cemented first stage with 350 sx 50:50 pozmix with 4% gel. POB 2:18 a.m. 11-10-60. Cntd second stage thru DV tool with 100 sx reg. POB 2:45 a.m. 11-10-60. Pressure to 2200 psi. Drilled DV tool and pressure to 1800 psi for 30 minutes. OK. Cleaned out to 6370' & released rig 11-11-60. WO completion unit.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company **NORTHWEST PRODUCTION CORPORATION**

Address **320 SINE BUILDING**
ALBUQUERQUE, N. M.

By _____

Title **RAY PHILLIPS, MGR., PROD. OPER.**