

(SUBMIT IN TRIPLICATE)

Indian Agency Navajo

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

Allettee 14-20-0603-6359

Lease No. \_\_\_\_\_

|   |    |  |
|---|----|--|
|   |    |  |
|   |    |  |
|   | 23 |  |
| x |    |  |

SUNDRY NOTICES AND REPORTS ON WELLS

|   |  |   |
|---|--|---|
| NOTICE OF INTENTION TO DRILL                  | SUBSEQUENT REPORT OF WATER SHUT-OFF        |   |
| NOTICE OF INTENTION TO CHANGE PLANS           | SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING |   |
| NOTICE OF INTENTION TO TEST WATER SHUT-OFF    | SUBSEQUENT REPORT OF ALTERING CASING       |   |
| NOTICE OF INTENTION TO REDRILL OR REPAIR WELL | SUBSEQUENT REPORT OF REDRILLING OR REPAIR  |   |
| NOTICE OF INTENTION TO SHOOT OR ACIDIZE       | SUBSEQUENT REPORT OF ABANDONMENT           | X |
| NOTICE OF INTENTION TO PULL OR ALTER CASING   | SUPPLEMENTARY WELL HISTORY                 |   |
| NOTICE OF INTENTION TO ABANDON WELL           |  |   |

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

February 23, 19 62

(Fruitland Navajo)

Well No. 1 is located 613 ft. from [N] line and 546 ft. from [E] line of sec. 23

SW/4, Section 23 T29N R15W NMPM  
(1/4 Sec. and Sec. No.) (Twp.) (Range) (Meridian)  
Wildcat San Juan County New Mexico  
(Field) (County or Subdivision) (State or Territory)

The elevation of the derrick floor above sea level is 5277 ft.


DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

The subject well was drilled to a T.D. of 4640'. A string of 8 5/8" O.D. surface pipe was set at 262' and cemented to surface with 125 sacks regular. Commercial production was not encountered and the well was plugged in the following manner:

4640' - 4575' w/ 90 sacks  
4250' - 4150' w/ 40 sacks  
1300' - 1200' w/ 40 sacks  
287' - 237' w/ 25 sacks  
10' - 0' w/ 10 sacks

The location was cleaned, pits were filled and a dry hole monument was properly erected.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Continental Oil Company

Address Box 3312

Durango, Colorado

Original Signed By:

By H. D. HALEY

Title District Superintendent

USGS(4) NMOCC(2) RLS GHG(5) HDH