

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other ☐

2. NAME OF OPERATOR

El Paso Natural Gas Company

3. ADDRESS OF OPERATOR

P.O. Box 289, Farmington, New Mexico 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE: 1650'N, 1650'W

AT TOP PROD. INTERVAL:

AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE
REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF ☐

FRACURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

CHANGE ZONES ☐

ABANDON* ☐

(other)

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

5. LEASE SF 078578-A	6. IF INDIAN, ALLOTTEE OR TRIBE NAME	7. UNIT AGREEMENT NAME	8. FARM OR LEASE NAME Howell K	9. WELL NO. 4A	10. FIELD OR WILDCAT NAME Blanco M.V.	11. SEC. T, R, M. OR BLK. AND SURVEY OR AREA Sec. 17, T-30-N, R-8-W	12. COUNTY OR PARISH N.M.P.M.	13. STATE New Mexico	14. API NO. San Juan	15. ELEVATIONS (SHOW DF, KDB, AND WD) 5908' GL
-------------------------	--------------------------------------	------------------------	-----------------------------------	-------------------	--	---	----------------------------------	-------------------------	-------------------------	---

1-17-79: TD 2946'. Ran 79 jts. 7", 20#, K-55 intermediate casing, 2935' set at 2946'. Cemented w/352 cu. ft. cement. WOC 12 hours; held 1200#/30 minutes. Top of cement 1320'.
1-20-79: TD 5291'. Ran 77 jts. 4 1/2", 10.5#, KS casing liner, 2494' set 2797-5291'. Float collar set 5274'. Cemented w/436 cu. ft. cement. WOC 18 hours.
3-13-79: PRTD 5214' (Bridge plug set at this depth.) Tested casing to 3500#. OK. Perforated Upper & Lower P.L. 4868, 4878, 4884, 4890, 4896, 4902, 4908, 4914, 4920, 4926, 4938, 4964, 4996, 5008, 5038, 5057, 5095, 5125, 5146, 5175, 5206' w/1 SPZ. Fraced w/71,000# 20/40 sand and 142,000 gal. water. Flushed w/6300 gal. water.

(OVER)

Subsurface Safety Valve: Mannu. and Type

18. I hereby certify that the foregoing is true and correct


SIGNED _____ TITLE _____ DATE _____

(This space for Federal or State official use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY: _____

See Instructions on Reverse Side

NMOCC



Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

GPO : 1976 O - 214-145

200035. POLICE AND MEMBERS OF ARMY

SECURITY SERVICE
DEPARTMENT OF THE ARMY
BANGKOK, THAILAND

DATE 11-11-64
20445 2-111