

SUPPLEMENT TO A.P.D. FOR
HANLEY "A" #1

The BOP stack will consist of a pipe ram, blind ram and a rotating head. The BOP stack and rotating head will be nipped up and pressure tested to 1000 psi, after cementing of the surface casing has been completed. Drilling will commence when it has been determined that the BOP stack will contain the test pressure. The BOP stack will be pressure tested to 1000 psi, when cementing of the intermediate casing string has been completed. Additional testing of the BOP stack will consist of daily mechanical checks of the pipe rams, and mechanical checks of the blind rams whenever the drill pipe is out of the hole.

BOP schematic on following page.



BLOWOUT PREVENTER SCHEMATIC

