

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS


(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other ☐
well well well
2. NAME OF OPERATOR
Tenneco Oil Company
3. ADDRESS OF OPERATOR
720 S. Colo. Blvd., Denver, CO 80222
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
825'FNL, 1660'FWL, Unit C
AT SURFACE:
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF ☐ ☐
FRACTURE TREAT ☐ ☐
SHOOT OR ACIDIZE ☐ ☐
REPAIR WELL ☐ ☐
PULL OR ALTER CASING ☐ ☐
MULTIPLE COMPLETE ☐ ☐
CHANGE ZONES ☐ ☐
ABANDON* ☐ ☐
(other) Plug and Sidetrack, Production casing Report

5. LEASE
SF-080245
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
Hamner
9. WELL NO.
2A
10. FIELD OR WILDCAT NAME
Dakota/Mesa Verde
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 28; T29N; R9W
12. COUNTY OR PARISH
San Juan
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
5721'GR

(NOTE: Report results of multiple completions or zone change on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

4/17/80

After several unsuccessful attempts to retrieve fish, elected to plug and sidetrack. TIH openended and tagged top of fish @ 4890. Spotted 75 sxs of CL-B cmt. w/15% 20/40 mesh sand and 3/4% CFR-2. WOC. Tagged plug @ 4800'. (Cmt plug: 4800-90) Drilled cmt to 4821' and began sidetrack. Wiped dogleg and resumed drilling down sidetracked hole. Reached TD of 6707 on 4/28/80. Ran and set 64 jts of 4 1/2", 10.5# 11.6# csg w/liner assembly @ 6714'. TOL: 4646. Cmt. w/170 sxs 50/50 Pozmix. Tailed w/150 sxs CL-B. Circ to 4646'. Released rig 4/30/80. WOCU.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Carley TITLE Admin. Supervisor DATE 5/2/80

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

MAY 28 1980

*See Instructions on Reverse Side

AMOC
SEAL

FARMINGTON DISTRICT
BY HA

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other ☐

2. NAME OF OPERATOR
Tenneco Oil Company

3. ADDRESS OF OPERATOR
720 S. Colo. Blvd., Denver, CO 80222

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 825'FNL, 1660'FWL, Unit C
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐

☐
☐
☐
☐
☐
☐
☐
☐

(other) Plug and Sidetrack, Production Casing Report

(NOTE: Report results of stimulation or completion or zone change on Form 9-330)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

4/17/80

6 1/4" hole drilled to a total depth of 4890. Attempt to set BP inside of 7" casing. Bridge plug parted in hole. Unable to recover fish after several attempts. Bridge plug pushed to bottom @ 4890. Fish left in hole 4890-4888. TIH open ended to top of fish. Spot 75 sx plug. 4888 to 4800. WOC. TIH & tag top of cement @ 4800 dressed off cement plug to 4821. TIH w/side tracking tools & sidetrack around fish @ 4839. Resume drilling to a total depth of 6707'

Subsurface Safety Valve: Manu. and Type _____

Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Curly Matheson TITLE Admin. Supervisor DATE 5/15/80

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

ACCEPTED FOR RECORD

MAY 28 1980

FARMINGTON DISTRICT
BY 7/8