

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other

2. NAME OF OPERATOR
Tenneco Oil Company

3. ADDRESS OF OPERATOR
Box 3249 Englewood, Co 80155

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1670' FNL 1120' FWL "E"
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:


16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:


TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☐
☒
☒
☐
☐
☐
☐
☐
☐



(NOTE: Report results of multiple completion or zone change on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

3/18/81. MIRUSU. Install BOP. RIH w/tbg and bit to drill out DV tool.
3/19/81. Drill out DV tool. Finish RIH w/tbg. Tagged cmt @ 5830'. Drill out to PBTD. Pressure test csg to 3500 PSI. Test good. Circ'd hole clean w/1% KCL water and spotted 500 gals 7½% DI-HCL @ 5849'. POOH w/tbg and bit.
3/20/81. Perf'd Dakota w/3-1/8" csg gun @ 2 JSPF as follows: 5690-95', 5699-5704', 5722-25', 5766-68', 5792-5805', 5830-34', 5838-43', 5847-49'. Established rate: 39BPM @ 3000 PSI. Acidized w/1600 gals 15% HCL, salt, and 126 ball sealers. Balled off. RIH w/wireline junk basket to PBTD. Frac'd Dakota w/80,000 gals 30# X-L gel, 1% KCL water, 80,000# 20/40 sand, 25,000# 10/20 sand. 1st AIR: 63 BPM AIP: 2900 PSI. 2nd AIR: 42 BPM AIP: 3300 PSI. ISIP: 1700 PSI, 15 min SIP: 1100 PSI
3/21/81. TIH and tag sand @ 5811. Clean out to PBTD w/foam. Land 2-3/8" tbg @ 5720. NDBOP. NUWH. RDMOSU.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Carley Patton TITLE Asst. Div. Adm. Mgr DATE March 26, 1981

(This space for Federal or State office use)

ACCEPTED FOR RECORD

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____ DATE _____

NMOCC

APR 09 1981

*See Instructions on Reverse Side

FARMINGTON DISTRICT

BY Carley Patton

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.