

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other ☐

2. NAME OF OPERATOR
Tenneco Oil Company


3. ADDRESS OF OPERATOR
P. O. Box 3249, Englewood, CO 80155

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 2400' FSL 1150' FWL
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:


16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:
TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) _____

SUBSEQUENT REPORT OF:



(NOTE: Report results of multiple completion or zone change on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

2/18/82 - RIH w/tbg & 2-7/8" swedge on btm & SN. Tagged SD @ 5460'. CO to model D pkr w/N2 & foam. Pld up to 5360' & landed tbg in BOP. Unable to get well to kick around w/N2. Made 1 swab run & well started flwg.

2/19/82 - Well flwg gas mist.

2/20/82 - Flwg to CU.

2/23/82 - Killed well w/1% KCL wtr. POOH w/tbg. RIH w/WL and set RBP @ 4850'. Dumped 2sx SD on top of RBP and loaded hole w/2% KCL wtr. Perf'd Chacra w/4" csg gun and 2 JSPP as follows: 4650-55', 4777-81', (9' - 18 holes).

2/24/82 - RIH w/tbg and 7" fullbore pkr to 4694'. Acidized dn tbg w/200 gal 15% wtd HCL and 12 ball slrs. Brk dn @ 1500 psi. Did not get complete ball off. Knocked balls off w/pkr and unloaded hole w/N2. Frac'd Chacra dn csg w/70% quality foma w/2% KCL wtr and 20/40 SD. Flushed to top perms. Ran RA SD in last stage of frace.

2/25/82 - Ran GR over Chacra perms. RIH w/tbg and tagged SD @ 4788'. CO to 4845' w/ N2 and foam. Landed tbg @ 4633'. Removed BOP & install WH. Kicked well around w/N2. Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

Flwg to CU. RDMOSU.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE production analyst DATE 3/4/82

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

*See Instructions on Reverse Side

NMOCC

MAR 10 1982

FARMINGTON DISTRICT
BY [Signature]