

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other

2. NAME OF OPERATOR
Tenneco Oil Company

3. ADDRESS OF OPERATOR
P. O. Box 3249, Englewood, CO 80155

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1300' FSL 1190' FWL
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐
☐

5. LEASE

SF-080000

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Florance

9. WELL NO.

126

10. FIELD OR WILDCAT NAME

Basin Dakota

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Sec. 26, T29N R9W

12. COUNTY OR PARISH

San Juan


13. STATE

New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
5626' gr.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

11/12/81 - MIRURT. Spud well w/Four Corners rig.

11/13/81 - Run 7 jts 9-5/8" 36# K-55 ST&C. Cmtd w/250 Cl-B w/2% cc and 1/4#/sx flocele. Circ cmt.

11/16/81 - Log.

11/17/81 - RU and run 86 jts 7" 23# K-55 ST&C set @ 3450'. Cmt w/390 sx lo-dense and 1/4#/sx flocele, tail w/200 sx Cl-G and 2% CACL.

11/21/81 - TD 6615'. RU and run 77 jts 4-1/2" 10.5# K-55 STC& csg. Set @ 6615'. Cmt w/300 sx Cl-B and 3% A-Z. Tail w/150 sx Cl-B. Circ cmt to surface. Rig release.

11/22/81 - WOCU.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Sandra Peron TITLE Production Analyst DATE 12/2/81

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____ DATE _____

ACCEPTED FOR RECORD

*See Instructions on Reverse Side

NMOCC

DEC 08 1981

FARMINGTON DISTRICT

BY Sam