

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form Approved.
Budget Bureau No. 42-R1424

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas ☒ well ☐ other
2. NAME OF OPERATOR
Amoco Production Company
3. ADDRESS OF OPERATOR
501 Airport Drive, Farmington, NM 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1570' FSL x 840' FEL
AT TOP PROD. INTERVAL: Same
AT TOTAL DEPTH: Same
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

5. LEASE SF-080491	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
7. UNIT AGREEMENT NAME Gallegos Canyon Unit	
8. FARM OR LEASE NAME	
9. WELL NO. 134E	
10. FIELD OR WILDCAT NAME Basin Dakota	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NE/4, SE/4, Section 17, T29N, R12W	
12. COUNTY OR PARISH San Juan	13. STATE New Mexico
14. API NO. 30-045-25222	
15. ELEVATIONS (SHOW DF, KDB, AND WD) 5694' G.L.	


REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) Spud & Set Casing

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐
☐

(NOTE: Report results of mud logging operation or zone change on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Spudded a 12-1/4" hole on 10-29-81 and drilled to 332'. Set 8-5/8" 24# surface casing at 332' on 10-30-81, and cemented with 280 sx of class "B" neat cement containing 2% CaCl2. Good cement was circulated to the surface. Drilled a 7-7/8" hole to a TD of 6405'. Set 4-1/2" 10.5# production casing at 6405', on 11-7-81, and cemented in two stages.

1) Used 335 sx of Class "B" neat cement containing 50:50 POZ, 6% gel, 2# medium tuf plug per sack, and .8% fluid loss additive. This was tailed in with 100 sx of class "B" neat cement. Good cement was circulated to surface.

2) Used 735 sx of class "B" neat cement containing 65:35 POZ, 6% gel,

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ OVER _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED E. E. SVOBODA TITLE Dist. Admin. Supvr DATE NOV 20 1981

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR RECORD

NOV 24 1981

FARMINGTON DISTRICT
BY SA

*See Instructions on Reverse Side

NMOCC

335
100
4735
1170

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

2# medium tuf plug per sack, and .8% fluid loss additive.
This was tailed in with 100 sx of class "B" neat cement.
No cement was circulated to the surface. Cement top is
900' below ground level.

The DV tool was set at 4583'.

The rig was released on 11-8-81.