

STATE of NEW MEXICO #2
TEN POINT PROGRAM, continued

Testing Program: No tests are planned.

Stimulation Program: Perforate the Pictured Cliffs with 4 JSPF and fracture stimulate with approximately 3000 lbs of frac sand per foot of perforated interval in either a 70 quality nitrogen foam system or a cross-linked gelled water system.

9. Abnormal Pressure: Although not expected, abnormal pressures are possible in the Farmington sand of the Kirtland formation.

Estimated Bottom Hole Pressure: 600 psig.

10. Anticipated Starting Date: As soon as all required approvals are received.

Duration of Operation: It is estimated that a total of 4 days will be required for drilling operations and 5 days for completion operations.
